

SCHEDULE OF WORKS

Name of the work - Construction of Pond Inside Tourism Project at Sadeibereni	
Amount put to Tender	- Rs.14,48,686.00/-
EMD	- Rs. 14,500/-
Cost of Tender Paper	- Rs. 6,720/-
Last Date of sale and receipt of Tender Paper	- 23.04.2018 Upto 7.00 AM
Date of opening of Tender Paper	-10 .05.2018 at 10.00 AM
Class of Contractor	- "D"and above
Time of Completion	- Three Calender Month

(This BOQ template must not be modified / replaced by the bidder, else the bidder is liable to be rejected for this tender, Bidders are allowed to enter the bidder name and values only)

Name of the Bidder -		Less -		(in %)
		Excess - Not allowed		

CIVIL WORKS

SL NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Excavation of foundation in laterite rock or any hard rock (other than granite or disintegrated rock) removed by chiselling including dressing and levelling the bed not exceeding 1.5m in depth and depositing the soil within initial lead of 50m with cost of labour, T.& P. etc. required for the work complete as per the specification and direction of the EIC	331.11	Cum	927.45	307087.9
2	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	27.32	Cum	448.02	12238.33
3	Providing & laying Cement Concrete (1:3:6) using 40mm crusher broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	27.32	Cum	4071.84	111228.75
4	RCC M-20 grade with crushed granite coarse aggregate of size 20 mm downgraded mixed in mixing plant with vibrator including cost of all materials, machineries & labour including cost, conveyance, labour, all taxes & royalty etc complete including centring & shuttering as per direction of E.I.C.				
	A) Raft	53.39	Cum	4702.47	251084.35
	B) RCC Wall	22.48	Cum	8838.98	198684.52
5	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars, cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge.(Weight of binding wire shall not be considered for payment in any shape at all).	52.13	Qtl.	5628.18	293397.02
6	Flyash Brick Masonry in Cement mortar (1:6) in F/P including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying, watering, curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	17.55	Cum	3479.85	61057.45

