

## SCHEDULE OF WORKS

<b>Name of the work - Completion of Entrance Lobby ,Reception &amp; Admin. Block at Sadeibereni</b>	
<b>Amount put to Tender</b>	<b>- Rs.15,09,533.00/-</b>
<b>EMD</b>	<b>- Rs. 15,100/-</b>
<b>Cost of Tender Paper</b>	<b>- Rs. 6,720/-</b>
Last Date of sale and receipt of Tender Paper	- 23.04.2018 Upto 7.00 AM
Date of opening of Tender Paper	-10 .05.2018 at 10.00 AM
Class of Contractor	- "D"and above
Time of Completion	- Three Calender Month

(This BOQ template must not be modified / replaced by the bidder, else the bidder is liable to be rejected for this tender, Bidders are allowed to enter the bidder name and values only)

Name of the Bidder -		Less -	(in %)		
		<b>Excess - Not allowed</b>			
<b>CIVIL WORKS</b>					
<b>SL NO</b>	<b>DESCRIPTION</b>	<b>QTY</b>	<b>UNIT</b>	<b>RATE</b>	<b>AMOUNT</b>
1	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm crusher broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	19.28	Cum	4071.84	78509.99
2	Supplying, fitting & fixing MS door & window shutter with grills (Framed&Fixed) made out of MS angles, flats and sheets etc of approved design & fabrication including cost, conveyance & taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of EIC	899.4	Kg	70	62957.66
3	16 mm thick cement plaster over brick masonry after racking out joints in cement mortar ( 1 : 6 ) including cost, conveyance, royalty & taxes etc. of all materials required for the work,watering, curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	305	Sqm	139.9	42707.19
4	Supplying, fitting & fixing Vitrified tiles 600mm x 600mm in floors ,treads or steps & landings on 25mm thick bed of cement mortar 1:1 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing including cost of tiles.....etc compl	29.78	Sqm	816.81	24326.90
5	Supplying, fitting & fixing Kadappa Tiles in floors ,treads or steps & landings on 25mm thick bed of cement mortar 1:1 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing including cost of tiles.....etc compl	523.3	Sqm	729.68	381839.94
6	Syppling, fitting & fixing Kadappa tiles in dado,skirting & rises of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost of Vitrified tiles & rubbing & polishing..etc compl.	67.32	Sqm	766.93	51631.14
7	Syppling, fitting & fixing Ceramic glazed tiles in dado,skirting & rises of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost of glazed wall tiles & rubbing & polishing.....etc compl.	140.88	Sqm	786.01	110733.87

