

**BoQ FOR THE WORK CONSTRUCTION OF CULVERT AT-LAMBODAR PUR SANSAILO
VILLAGE, BHALIABOLKATANI**

Srl. No.	Item Description	Quantity	Units	Estimated Rate	Amount	Total Amount in Word
1	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site within 50 M initial lead and 1.5 M initial lift with cost of labour, T. & P. etc. required for the work complete as per the specification and direction of the EIC	64.87	Cum	193.45	12549.10	INR Twelve thousand five hundred forty nine rupee and ten paise only
2	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	9.41	Cum	362.8	3413.95	INR Three thousand four hundred thirteen rupee thirty ninty five paise on lv
3	Providing & laying Cement Concrete (1:3:6) using 40mm crusher broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	133.110	Cum	4955.58	659637.25	INR Six lakh fifty nine thousand six hundred thirty seven rupee & twenty five paise only
4	RCC M-20 grade with crushed granite coarse aggregate of size 20 mm downgraded mixed in mixing plant with vibrator including cost of all materials, machineries & labour including cost, conveyance, labour, all taxes & royalty etc complete as per direction of E.I.C.	6.9	Cum	5238.47	36145.44	INR Thirty six thousand one hundred forty five rupee & forty four paise only

5	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars, cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge. (Weight of binding wire shall not be considered for payment in any shape at all).						
		6.9	Qntl	9026.46	62282.57		INR Sixty two thousand two hundred eighty two rupee & fifty seven paise only
6	Rigid & smooth centering & shuttering for R.C.C work including false work & dismetalling then after casting & curing for 21 days including cost & carriage royalty etc of all materials required for the work etc. as per the specification & direction of E-I-C.						
	Head wall, wing wall	150.18	sqm	105.71	15875.53		INR Fifteen thousand eight hundred seventy five rupee & fifty two paise only
	Slab	22.19	sqm	425.03	9431.42		INR Nine thousand four hundred thirty one rupee & forty two paise only
	Total				799335		INR Seven lakh ninty nine thousand three hundred thirty five only
	Quoted Rate in Figures	Total					799335
	Quoted Rate in words				799335		INR Sevent lakh ninty nine thousand three hundred thirty five only

Approved for 6 items only

Notes:-The contractor should not write any thing except quoting of percentage.Excess /Less/Equal to estimate up to two decimal points only

CONDITIONS-All materials,Labours Machinery & equipment required to complete the work in all respect be arrange by the tenderer at his own cost.The employer will bear no responsibility in this aspect.

* N/B- GST Income Tax Royalty Labour cess as applicable will be deducted from the soil of the contractor for all above works the minimum grades of cement shall be opTMT High strength steel Fe 500 like SAIL/TISC



J.E
Sadar Block
Dhenkanal



A.E.
Sadar Block
Dhenkanal



B.D.O
Sadar Block
Dhenkanal