


**GOVERNMENT OF ODISHA**  
**PR & DW, DEPARTMENT**



**OFFICE OF THE PANCHAYAT SAMITI, BHUBAN**  
**BID DOCUMENT**  
**BID IDENTIFICATION NO – 03/2022-23**  
**NAME OF WORK**

1	2	4
1	Const. of Model Pond at Anal	Rs.5,42,392
2	Improvement & Renovation of Jorgadia Pokhari	Rs.5,65,374
3	Const. of Adarsha Pokhari at Khantakhole near Siva Mandir	Rs.5,64,192
4	Improvement & Renovation of Mathakhoksha Badabandha	Rs.5,63,777
5	Improvement & Renovation of Belapal Pokhari	Rs.5,64,386
6	Improvement & Renovation of Dayanabili Panubereni Pokhari	Rs.5,64,390
7	Renovation of Kuninda Bada Pokhari as Model Unit	Rs.5,63,645
8	Development of Adarsha Pokhari and Park near Kuninda Siva Mandir	Rs.7,78,688
9	Development of Adarsha Pokhari Basudeipur	Rs.8,06,920
10	Renovation and Improvement of Dhalapada Pota Pokhari	Rs.7,83,901

  
BLOCK DEVELOPMENT OFFICER,  
BHUBAN

**GOVERNMENT OF ODISHA**  
**INVITATION FOR BIDS (IFB)**

Identification No. 03/2022-23 of Panchayat Samiti, Bhuban  
TENDER CALL NOTICE NO. 2022-23

E-Mail ID -ori-bhuban@nic.in

1. Block Development Officer, Bhuban invites percentage (%) sealed tenders in conformity with the Tender Call notice(TCN) from the registered contractors of state PWD/M.I/Irrigation /Rural works/CPWD/PHD/for the following works under Bhuban Block to be eventually drawn in PWD F-2 (Now P-1) contract as detailed below. The amount put to tender and bid security may be changed and confirmed at the time of selling of tender documents. Bid identification No-03/2022-23/BDO, Bhuban.

Sl No.	Name of the Work	Approximate value of work (In lakhs)	Class of Contract or	Place of sale and receipt of tender papers	E.M.D in Rs.	Cost of documents (Non-refundable) in Rs	Period of completion in months
1	2	4	5	6	7	8	9
1	Const. of Model Pond at Anal	Rs.5,42,392	'C' & 'D'	Office of the Panchayat Samiti, Bhuban	5424/-	Rs.4000/-	03(Three Calendar Months)
2	Improvement & Renovation of Jorgadia Pokhari	Rs.5,65,374	'C' & 'D'	-do-	5654/-	Rs.4000/-	03(Three Calendar Months)
3	Const. of Adarsha Pokhari at Khantakhole near Siva Mandir	Rs.5,64,192	'C' & 'D'	-do-	5642/-	Rs.4000/-	03(Three Calendar Months)
4	Improvement & Renovation of Mathakhoksha Badabandha	Rs.5,63,777	'C' & 'D'	-do-	5638/-	Rs.4000/-	03(Three Calendar Months)
5	Improvement & Renovation of Belapal Pokhari	Rs.5,64,386	'C' & 'D'	-do-	5644/-	Rs.4000/-	03(Three Calendar Months)
6	Improvement & Renovation of Dayanabili Panuberani Pokhari	Rs.5,64,390	'C' & 'D'	-do-	5644/-	Rs.4000/-	03(Three Calendar Months)
7	Renovation of Kuninda Bada Pokhari as Model Unit	Rs.5,63,645	'C' & 'D'	-do-	5636/-	Rs.4000/-	03(Three Calendar Months)
8	Development of Adarsha Pokhari and Park near Kuninda Siva Mandir	Rs.7,78,688	'C' & 'D'	-do-	7787/-	Rs.4000/-	03(Three Calendar Months)
9	Development of Adarsha Pokhari Basudeipur	Rs.8,06,920	'C' & 'D'	-do-	8620/-	Rs.4000/-	03(Three Calendar Months)
10	Renovation and Improvement of Dhalada Pota Pokhari	Rs.7,83,901	'C' & 'D'	-do-	7839/-	Rs.4000/-	03(Three Calendar Months)



## Term & Conditions:

1. **Cost of Tender paper:** The tenders specification can be obtained from the office of the Block Development Officer, Bhuban on payment towards the cost of tender paper as mentioned above.(Non- Refundable) in shape of Cash/ Bank draft / Demand draft (No other modes will be entertained) drawn in favour of Block Development Officer, Bhuban in any nationalized bank having its branch at Bhuban Block area on any working day from 24.03.2023 to 05.04.2023 for the above works.
2. **Sale of Tender Papers:** The tender document will be sold from at Panchayat Samiti, Bhuban from 24.03.2023 to 05.04.2023 between 11:00 AM to 5:30 PM on working days only.
3. **Date of receipt & Mode of submission of tender papers:** The bidders have to submit the sealed tender papers in complete shape through registered post/ Speed post/ tender box( Available at Block Office) to pay directly sending to the Block Development Officer, Bhuban. The last date of receipt of tender paper 05.04.2023 up to 05:30PM. The undersigned will not be responsible for postal delay if any or non receipt of papers in time. **The tender must super scribe the name of the work/ project on the sealed envelope.**
4. **Date of opening of tender papers:** The tender paper shall be opened on 10.04.2023 at 11:00AM in the presence of bidders or their authorized representative having written authorization for the purpose & the members of the tender committee.
5. **Earnest Money Deposit:** 1% (One Percent) of the bid value in shape of NSC/Postal saving pass book/ Post office Time Deposit/ Kishan Vikash Patra/ Deposit receipt in schedule bank only, duly pledged in favour of Block Development officer, Bhuban. The tender papers without required amount of E.M.D will not be considered & transfer or adjustment of E.M.D is also inadmissible.
6. **Documents to be attached:** The following documents should be furnished along with the tender papers failing which the tender is liable for rejection.
  - a) EMD pledged in favour of the Block Development Officer, Bhuban.
  - b) Self-attested copy of contractor registration certificate.
  - c) No relation certificate to the Block Development Officer, Bhuban
  - d) Self-attested copy of PAN cards and GSTIN, GST reg. certificate
  - e) Original money receipt granted by BDO, Bhuban towards cost of tender paper.
  - f) The bidders have to produce an original affidavit in support of the authenticity of documents including EMD, etc attached with the tender papers.
  - g) Affidavit as regards the facts of availing award of the work without submission of EMD/ISD during the current financial year in case of Engineer contractors desirous of availing exemption of EMD otherwise their tender paper will be liable for rejection.
  - h) Attested copy of Caste certificate issued by competent authority in case of SC/ST contractor desirous of availing preference.
7. Shortfall of any required documents & EMD, the tender paper will be liable for rejection.
8. **Additional Performance Security Deposit:** The affidavit in lieu of APS will be submitted by the successful bidder for the cost of less quoted percentage of the amount put to tender before the signing of the agreement of the contract. ( Vide works Deptt. letter no.13286 date 07.09.2017, Govt. of Odisha,)
9. **Forfeiture:** The EMD amount will be forfeited, if the bidders back out from the offer acceptance of tender, by the competent authority.
10. Submission of more than one tender paper by a bidder for a single work will be liable for rejection of all such tender papers.
11. **All the tenders where rate quoted is "15%" and above the scheduled rate will be rejected. ( Vide works Deptt. letter no.1437 date 31.01.2023, Govt. of Odisha,)**
12. The quoted percentage rate should be mentioned clearly in figure and words.



13. Other details can be seen in the bidding documents.

14. The Block Development officer, Bhuban reserves the right to reject any or all the tenders without assigning any reasons thereof.

Memo No. 947 /Dt. 21.03.2023

Copy submitted to the Collector, Dhenkanal/SP, Dhenkanal/CDO-cum-EO, ZP, Dhenkanal/Sub-Collector, Kamakhyanagar/ Sub-Collector, Dhenkanal Sadar/ Sub-Collector, Hindol with request to display the above notice in the office notice Board for wide publication.

  
Block Development Officer  
Bhuban 21/03/23

Memo No. 948 /Dt. 21.03.2023

Copy submitted to Director, I & PR Deptt., Govt. of Odisha, Bhubaneswar for wide publication in one local English Daily and two Nos. of leading local Odia Daily newspapers.

  
Block Development Officer  
Bhuban 21/03/23

Memo No. 949 /Dt. 21.03.2023

Copy submitted to DIO, NIC, Dhenkanal for hoisting the notice on District website.

  
Block Development Officer  
Bhuban 21/03/23


Memo No. 950 /Dt. 21.03.2023

Copy Submitted to BDO, Gondia/ BDO, Dhenkanal Sadar/ BDO, Odapada/ BDO, Hindol/ BDO, Kankadahad/ BDO, Kamakhyanagar/ BDO, Parjang / ICDS, Bhuban/ NAC, Bhuban/ IIC, Bhuban Police Station/ Contractor Association, Dhenkanal / All Tahasildars of Dhenkanal District, with a request to display one copy the above notice on their office Notice Board and circulate among the local contractors for wide publication.

  
Block Development Officer  
Bhuban 21/03/23

Memo No. \_\_\_\_\_ /Dt. \_\_\_\_\_

Copy to the Asst. Executive Engineer, Bhuban Block/ Accounts Officer/ SO/ Cashier/ Notice Board of Bhuban Block Office.

  
Block Development Officer  
Bhuban 21/03/23

**NAME OF WORK:- Const of Model Pokhari at Anal**

**AMOUNT PUT TO TENDER:-**

**Rs. 542392.00**

SL No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation of any approved type of soil in approved borrow area by mechanical means loading into and transportation by mechanical means and unloading the soil within initial lead of 5 km on properly prepared and scientifically approved surface including spreading and levelling the earth in 22.5 cm layers to make ready for watering and compaction with sheep foot rollers and dozers but excluding watering and compaction in dams and dykes for all heights including	262.50	Cum	159.59	(Rupees One Hundred Fiftynine and Fiftynine Paise) Only	Rs 41892.00
2	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site within 50 M initial lead and 1.5 M initial lift with cost of labour, T.& P etc required for the work complete	12.15	Cum	199.58	(Rupees One Hundred nintynine and Fifty Eight Paise) Only	Rs 2425.00
3	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	2.03	Cum	369.37	(Rupees Three hundred Sixtynine and thirtyseven Paise) Only	Rs 750.00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	22.65	Cum	4883.51	Rupees Four Thousand Eight Hundred eighty three and Fifty One Paise) Only	Rs. 110633.00
5	Rigid & smooth centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	90.000	Sqm	107.58	Rupees One Hundred Seven and FiftyEight Paise) Only	Rs 9682.00
6	Rough stone dry packing in aprons and revetments with hard granite stones (15cm to 30cm)	220.575	Sqm	1709.22	Rupees One Thousand Seven Hundred Nine and	Rs 377010.00

TOTAL Rs 542392.00  
Say, Rs 542392.00

( Ruppess Five Lakh Fourty two Thousand Three hundred Ninty two ) Only

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess over /  
Less than / Equal to the above estimated cost and tendered amount is Rs. \_\_\_\_\_ Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_ pages



Notes - The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only

CONDITIONS - All materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect

N B - GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISCO

CONTRACTOR

  
BLOCK DEVELOPMENT  
OFFICER, BHUBAN

**NAME OF WORK:- Imp & Renovation of Joragadia Pokhari**

**AMOUNT PUT TO TENDER:-**

**Rs. 565374.00**

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation, loading, unloading and carriage by mechanical means of A.K.S, including Stoney eart, gravel and moorum etc with all lifts and delifts including trimming of slopes and bed to design section and depositing the excavated materials away from work siteand spreiding with Motor Grader as per the specification and direced by the Engineer-in-charge within an initial lead of 1 Km. from the place of excavation complete. (Excluding GST OF Machinaries)	1960.00	Cum	54 98	(Rupees FiftyFour and NintyEight Paise) Only	Rs. 107761 0
2	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site withen 50 M initial lead and 1.5 M initial lift with cost of labour, T.& P. etc. required for the work complete	62.98	Cum	199.58	(Rupees One Hundred Nintynine and Fifty Eight Paise) Only	Rs. 12569.00
3	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	15.53	Cum	369.37	(Rupees Three hundred Sixtynine and thirtySeven Paise) Only	Rs. 5734.00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	69.08	Cum	4883.51	Rupees Four Thousand eight Hundred eighty thren and Fifty one Paise) Only	Rs. 337328.0
5	Providing & laying Cement Concrete ( 1:2:4 ) using 12mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing for 21 days, labour charges etc. complete as per the specification & direction of EIC	11.576	Cum	6319.82	Rupees Six Thousand Three Hundred Nineteen andeighty two Paise) Only	Rs. 73158.0
6	Rigid & smooth centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	267.940	Cum	107.58	Rupees One Hundred Seven and Fifty eight Paise) Only	Rs. 28824.00
<b>TOTAL</b>						<b>Rs. 565374 0</b>
Say,						<b>Rs. 565374 0</b>

( Ruppes Five Lakh Ninetyfour Thousand fiftyseven ) Only

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess  
 over / Less than / Equal to the above estimated cost and tendered amount is Rs. ....  
 ..... Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

CONTRACTOR

  
BLOCK DEVELOPMENT  
OFFICER, BHUBAN

NAME OF WORK:- Const Of Adarsa Pokhari at Khantakhol near Siva Mandir

AMOUNT PUT TO TENDER:-

Rs. 564192.00

Sl No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation, loading, unloading and carriage by mechanical means of A.K.S, including Stony eart, gravel and moorum etc with all lifts and delifts including trimming of slopes and bed to design section and depositing the excavated materials away from work siteand spreading with Motor Grader as per the specification and directed by the Engineer-in-charge within an initial lead of 1 Km. from the place of excavation complete. (Excluding GST OF	1146.38	Cum	54.05	(Rupees Fiftyfour and Five Paise) Only	61965.00
2	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site withen 50 M initial lead and 1.5 M initial lift with cost of labour, T.& P. etc. required for the work complete	78.84	Cum	199.58	(Rupees One Hundred Nintynine and Fiftyeight Paise) Only	Rs. 15735.00
3	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work. labour charges etc. complete as per the specification & direction of EIC	13.14	Cum	369.37	(Rupees Three hundred Sixtynine and thirtySeven Paise) Only	Rs. 4854.00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	88.70	Cum	4883.51	Rupees Four Thousand Eight Hundred eighty Three and fiftyOne Paise) Only	Rs. 433143.00
5	Rigid & smooth centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	438.000		107.58	Rupees One Hundred Seven and FiftyEight Paise) Only	Rs. 47119.00
6	Filling Foundation and plinth with excavated materials including watering and ramming as directed by the EIC	12.410	Cum	110.88	Rupees One Hundred ten and Eighty eight Paise) Only	1376.00
					TOTAL	Rs 564192.00
					Say,	Rs 564192.00

( Ruppees Five Lakh Sixtyfourfour Thousand One hundred Ninty two ) Or

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess over  
Less than / Equal to the above estimated cost and tendered amount is Rs .....  
.....Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_pages



two decimal points only.

CONDITIONS :- All materials, Labour, Machineries and Equipments required to complete the work in all respects by the tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor. For works the minimum grade of cement shall be OPC. TMT High strength steel Fe - 500 like SAIL. TISCO



**BLOCK DEVELOPMENT  
OFFICER, BHUBANESHWAR**

**CONTRACTOR**



NAME OF WORK:-

Renovation &amp; Imp of Mathakhoksa BadaBandha

AMOUNT PUT TO TENDER:-

Rs. 563777.00

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation, loading, unloading and carriage by mechanical means of A.K.S, including Stoney eart, gravel and moorum etc with all lifts and delifts including trimming of slopes and bed to design section and depositing the excavated materials away from work siteand spreding with Motor Grader as per the specification and direced by the Engineer-in-charge within an initial lead of 1 Km. from the place of excavation complete. (Excluding GST OF	706.80	Cum	54.05	(Rupees Fiftyfour and Five Paise) Only	38204 00
2	Excavation of founation in laterite rock or any hard rock (other than granite or disintigrated rock) removed by chiselling including dressing and levelling the bed not exceeding 1.5m in depth and depositing the soil within initial lead of 50m with cost of labour, T.& P. etc. required for the work complete as per the specification and direction of the EIC	23.85	Cum	1446.56	(Rupees One Thousand Four Hundred fourtySix and Fiftysix Paise) Only	Rs. 34500.00
3	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	1.59	Cum	369 37	(Rupees Three hundred Sixtynine and thirtySeven Paise) Only	Rs. 587.00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	26.24	Cum	4883.51	Rupees Four Thousand Eight Hundred eighty Three and fiftyOne Paise) Only	Rs. 128119.00
5	RCC M-20 grade with crushed granite coarse aggregate of size 20 mm downgraded mixed in mixing plant with vibrator including cost of all materials, machineries & labour including cost, conveyance, labour, all taxes & royalty etc complete as per direction of E.I.C.	43.223	Cum	5128.16	Rupees Five Thousand One Hundred twenty eight Sixteen Paise) Only	Rs. 221652 00
6	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars, cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge.( Weight of binding wire shall not be considered for	14.500	Qtl	8455.86	Rupees Eight Thousand Four Hundred fiftyfive EightySix Paise) Only	Rs. 122610 00

(4)

TOTAL Rs 563777 00  
Say. Rs. 563777 00

( Ruppes Five Lakh Sixtyfourfour Thousand One hundred Ninty two ) Only

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs. ....  
.....Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

CONTRACTOR

  
BLOCK DEVELOPMENT  
OFFICER, BHUBAN

**NAME OF WORK:- Imp & Renovation of Belapal Pokhari****AMOUNT PUT TO TENDER:-****Rs. 564386.00**

SL No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation, loading, unloading and carriage by mechanical means of A.K.S, including Stony eart, gravel and moorum etc with all lifts and delifts including trimming of slopes and bed to design section and depositing the excavated materials away from work siteand spreiding with Motor Grader as per the specification and direced by the Engineer-in-	1040.00	Cum	54 98	(Rupees Fifty Four and Ninty eight Paise) Only	Rs 57179 00
2	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site withen 50 M initial lead and 1.5 M initial lift with cost of labour, T.& P. etc. required for the work complete	83.16	Cum	199 58	(Rupees One Hundred nintynine and Fifty eight Paise) Only	Rs 16597 00
3	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	13.86	Cum	369 37	(Rupees Three hundred sixtynine and thirtyseven Paise) Only	Rs. 5119.00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge	88.94	Cum	4883.51	Rupees Four Thousand Eight Hundred eighty thre and fifty one Paise) Only	Rs. 434339 00
5	Rigid & smooth centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	462.000		107.58	Rupees One Hundred Seven and Fifty eight Paise) Only	Rs. 49701.00
6	Filling Foundation and plinth with excavated materials including watering and ramming as directed by the EIC.	13.090	Cum	110.88	Rupees One Hundred ten and Eighty eight Paise) Only	Rs. 1451 00

TOTAL Rs. 564386 00

Say, Rs 564386 00

( Ruppes Five Lakh Sixtyfour Thousand Three hundred EightySix ) Only

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs \_\_\_\_\_ Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.



5

CONDITIONS :- All materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

CONTRACTOR



BLOCK DEVELOPMENT  
OFFICER, BHUBAN



NAME OF THE WORK- Reno. And Imp. Of Panubereni Pokhari, Dayanabil  
AMOUNT PUT TO TENDER- Rs.

SL NO	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation, loading, unloading and carriage by mechanical means of all kinds of soil, including stoney earth, gravel and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineerin- charge within an initial lead from the place of excavation complete					
A.	Depositing earth withen 1.0KM initial Lead	576.00	Cum	59.80	Rupees (Fifty-nine and Eighty Paise) only	34444.6
B.	Depositing earth withen 3.0KM initial Lead	432.00	Cum	102.50	Rupees (One Hundred two and Fifty Paise) only	44281.0
2	Excavation, loading and carriage by mechanical means in D.I. rock, laterite and soft rock not requiring blasting interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead from the place of excavation complete.	288.00	Cum	131.81	Rupees (One Hundred Thirtyone and Eightyone Paise) only	37961.41
3	Sprading & dozing of excavated earth in embankment in layers not exceeding 0.3m as per direction of EIC	576.00	Cum	14.48	Rupees (Forteen and Fortyeight Paise) only	8342.93
4	Earth work excavation of foundation in hard soil or gravelly soil withen 50 M initial lead and 1.5 M initial lift including rough dressing & breaking clods to maxm. 5cm to 7cm & laying in layers not exceeding 0.3m in depth etc. complete as per the specification and direction of the EIC	46.66	Cum	197.60	Rupees (One Hundred Nintyseven and Sixty Paise) only	9219.82
5	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of Engineer in charge.	10.46	Cum	372.57	Rupees (Three Hundred Seventytwo and Fiftyseven Paise) only	3896.34
6	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm crusher broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc.	52.91	Cum	5228.09	Rupees (Five Thousand Two Hundred Twentyeight and Zeronone Paise) only	276599.94

7	Providing & laying Cement Concrete ( 1:2:4 ) using 12mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing for 21 days, labour charges etc. complete as per the specification & direction of EIC	2.41	Cum	6825.59	Rupees (Six Thousand Eight Hundred Twentyfive and Fiftynine Paise) only	16442.85
8	Rigid smooth centring & shuttering for CC work including false work & dismantling then after casting including all cost...etc compl.	169.01	sqm	106.51	Rupees (One Hundred Six and Fiftyone Paise) only	18000.72
9	Rough stone dry packing in aprons and revetments with hard granite stones ( 15cm to 30 cm ) including all cost...etc compl.	65.25	Cum	1581.61	Rupees (One Thousand Five Hundred Eightyone and Sixtyone Paise) only	103200.02
10	Constn.of signboard & photography	1	No	5000.00	Rupees (Five Thousand ) only	5000.00
11	Add for CESS					7000.00
						564389.69
					Limited to	564390.00

Rupees( Five Lakh Sixtyfour Thousand Three Hundred Ninety) Only

My /Our quoted rate of \_\_\_\_\_ (both in figures & words) Excess over/Less than/Equal to the above estimated cost and tendered amount is Rs..... only

Total No. of pages (Enclosed) other than DTCN \_\_\_\_\_ pages.

Notes:- The Contractor should not write any thing except quoting of Percentage, Excess/Less/Equal to Estimate up to two decimal points only.

CONDITIONS:- All materials .Labour, Machineries and Equipments required to complete the waork in all respect arranged by the tenderer at this own cost. The Employer will bear no responsibility in this aspect.

N.B:- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for above works the minimum grade of cement shall be OPC, TMT High strength steel Fe-500 like SAIL/TISC.

Contractor-

  
Block Development Officer  
Bhuban Block

**NAME OF WORK:- Renovation of Kuninda Bada Pokhari as Model Unit**

**AMOUNT PUT TO TENDER:-**

**Rs. 563645.00**

SL No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation of any approved type of soil in approved borrow area by mechanical means loading into and transportation by mechanical means and unloading the soil within initial lead of 5 km on properly prepared and scientifically approved surface including spreading and levelling the earth in 22.5 cm layers to make ready for watering and compaction with sheep foot rollers and dozers but excluding watering and compaction in dams and dykes for all heights including construction, maintenance, watering and lighting of haul road and borrow area etc. complete as per the direction of Engineer-in charge( Measurement of the fill to be taken on the finished compacted section under OMC Condition.)(As per AR-2006, page-11, item-1 )	213.30	Cum	159.59	(Rupees One Hundred Fifty Nine and Fiftynine Paise) Only	Rs 34040 00
2	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site within 50 M initial lead and 1.5 M initial lift with cost of labour, T.& P. etc. required for the work complete	31.40	Cum	199.58	(Rupees One hundred Ninty nine and Fifty eight Paise) Only	Rs. 6267 00
3	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	41.34	Cum	369.37	(Rupees Three hundred sixtynine and thirtyseven Paise) Only	Rs 15270 00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	23.18	Cum	4883.51	Rupees Four Thousand eight Hundred eighty three and fifty One Paise) Only	Rs 113175 00
5	Rigid & smooth centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	308.640	Cum	107.58	Rupees One Hundred seven and Fifty Eight Paise) Only	Rs 33203 00
6	Providing & laying Cement Concrete ( 1:2:4 ) using 12mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing for 21 days, labour charges etc. complete as per the specification & direction of EIC	10.22		6319.82	Rupees Six Thousand three Hundred nineteen and eightytwo Paise) Only	Rs 64563 00

Providing and Laying 80 mm thick Factory Made Cement Concrete Interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction of approved size design and shape laid in required colour and part on over and including 50 mm thick compacted bed of coarse sand and filling the joints with fine sand etc. Complete as per direction of EIC.	330 15	Sqm	899 98	Rupees Eight Hundred Nintynine and NintyEight Paise) Only	Rs 297127 00
---	--------	-----	--------	---	--------------

TOTAL Rs 563645 00  
 Say, Rs 563645 00

( Ruppes Five Lakh Sixty three Thousand Six hundred fourtyfive ) Only

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs \_\_\_\_\_ Only

Total No of pages ( Enclosed ) other than DTCN \_\_\_\_\_ pages

Notes - The Contractor should not write any thing except quoting of Percentage . Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N B - GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

CONTRACTOR



BLOCK DEVELOPMENT OFFICER,  
 BHUBAN

NAME OF WORK:- Dev of Adarsa Pokhari & Park near Kuninda Siva Mandir

AMOUNT PUT TO TENDER:-

Rs. 778688:00

SL No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation of any approved type of soil in approved borrow area by mechanical means loading into and transportation by mechanical means and unloading the soil within initial lead of 5 km on properly prepared and scientifically approved surface including spreading and levelling the earth in 22.5 cm layers to make ready for watering and compaction with sheep foot rollers and dozers but excluding watering and compaction in dams and dykes for all heights including construction, maintenance, watering and lighting of haul road and borrow area etc. complete as per the direction of Engineer-in charge (Measurement of the fill to be taken on the finished)	433.60	Cum	159.59	(Rupees One Hundred Fifty Nine and Fiftynine Paise) Only	69198.00
2	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site within 50 M initial lead and 1.5 M initial lift with cost of labour, T. & P. etc. required for the work complete	67.23	Cum	199.58	(Rupees One Hundred nintynine and Fifty eight Paise) Only	Rs. 13418.00
3	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	11.21	Cum	369.37	(Rupees Three hundred Sixtynine and thirtyseven Paise) Only	Rs. 4141.00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	85.92	Cum	4883.51	Rupees Four Thousand eight Hundred eighty three and Fifty one Paise) Only	Rs. 419611.00
5	Rigid & smooth centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	498.000		107.58	Rupees One Hundred seven and Fifty Eight Paise) Only	Rs. 53574.00
6	Filling Foundation and plinth with excavated materials including watering and ramming as directed by the EIC.	14.110	Cum	110.88	Rupees One Hundred ten and Eighty eight Paise)	Rs. 1565.00
7	Rough stone dry packing in aprons and revetments with hard granite stones (15cm to 30cm)	127.06	Cum	1709.22	Rupees One Thousand seven Hundred nine and twenty two Paise) Only	Rs. 217181.00

TOTAL Rs. 778688.00  
Say, Rs. 778688.00



( Ruppes Seven Lakh Seventy Eight Thousand Six hundred Eightyeight ) On

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess over  
Less than / Equal to the above estimated cost and tendered amount is Rs \_\_\_\_\_  
.....Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

CONTRACTOR

  
BLOCK DEVELOPMENT  
OFFICER, BHUBAN

NAME OF WORK:- Dev of AdarsaPokhari Basudeipur

AMOUNT PUT TO TENDER:-

Rs. 806920.00

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation of any approved type of soil in approved borrow area by mechanical means loading into and transportation by mechanical means and unloading the soil within initial lead of 5 km on properly prepared and scientifically approved surface including spreading and levelling the earth in 22.5 cm layers to make ready for watering and compaction with sheep foot rollers and dozers but excluding watering and compaction in dams and dykes for all heights including construction, maintenance, watering and lighting of haul road and borrow area etc. complete as per the direction of Engineer in charge/ Measurement of the	326.40	Cum	159.59	(Rupees One Hundred Fifty Nine and Fiftynine Paise) Only	52090.00
2	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site within 50 M initial lead and 1.5 M initial lift with cost of labour, T.& P. etc. required for the work complete	108.54	Cum	199.58	(Rupees One Hundred nintynine and Fifty eight Paise) Only	Rs. 21662.00
3	Filling foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	18.09	Cum	369.37	(Rupees Three hundred Sixtynine and thirtyseven Paise) Only	Rs. 6682.00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	131.05	Cum	4883.51	Rupees Four Thousand eight Hundred eighty three and Fifty one Paise) Only	Rs. 639994.00
5	Rigid & smooth centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	804.000		107.58	Rupees One Hundred seven and Fifty Eight Paise) Only	Rs. 86492.00

TOTAL Rs. 806920.00  
Say, Rs. 806920.00

( Ruppes Eight Lakh Six Thousand nine hundred Twenty )

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess over  
Less than / Equal to the above estimated cost and tendered amount is Rs. \_\_\_\_\_

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less Equal to Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machineries and Equipments required to complete the work in all respect arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

CONTRACTOR



BLOCK DEVELOPMENT  
OFFICER, BHUBAN

# NAME OF WORK:- Renovation & Imp of Dhalapada Pota Pokhari

AMOUNT PUT TO TENDER:-

Rs. 783901.00

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Excavation, loading, unloading and carriage by mechanical means of A.K.S, including Stony earth, gravel and morum etc with all lifts and delifts including trimming of slopes and bed to design section and depositing the excavated materials away from work site and spreading with Motor Grader as per the specification and directed by the Engineer-in-charge within a initial lead of 1 Km. from the place of excavation complete. (Excluding GST OF 12% machines)	1238.40	Cum	54.05	(Rupees Fiftyfour and Five Paise) Only	Rs. 66939.00
2	Earth work excavation of foundation in hard soil rough dressing & levelling bed & depositing the excavated earth away from work site within 50 M initial lead and 5 M initial lift with cost of labour, T.& P. etc. required for the work complete	115.56	Cum	199.58	(Rupees One Hundred Nintyninet and fifty eight Paise) Only	Rs. 23063.00
3	Finishing foundation & plinth with filling sand well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	19.26	Cum	369.37	(Rupees Three hundred Sixty-nine and thirtyseven Paise) Only	Rs. 7114.00
4	Providing & laying Cement Concrete ( 1:3:6 ) using 40mm Hand broken granite metal including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	130.01	Cum	4883.51	Rupees Four Thousand eight Hundred eighty three and fifty one Paise) Only	Rs. 634881.0
5	Providing & laying Cement Concrete ( 1:2:4 ) using 12mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing for 21 days, labour charges etc. complete as per the specification & direction of EIC	2.41	Cum	6319.82	Rupees six r Thousand Three Hundred nineteen and Eightytwo Paise) Only	Rs. 15215.00
5	Formwork centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	322.300		107.58	Rupees One Hundred seven and Fiftyeight Paise) Only	Rs. 34672.00
6	Finishing Foundation and plinth with excavated materials including watering and ramming as directed by the EIC	18.190	Cum	110.88	Rupees One Hundred ten and Eighty eight Paise) Only	Rs. 2017.00

TOTAL Rs. 783901.0  
Say, Rs. 783901.0



( Rupees Seven Lakh Eighty three Thousand Nine hundred One )

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words ) Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs. ....  
..... Only

Total No. of page ( Enclosed ) other than DTCN \_\_\_\_\_ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS - All materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

CONTRACTOR

  
BLOCK DEVELOPMENT  
OFFICER, BHUBAN