

Name of the work :- Stepped Pathway with both side Railing

Amount Put To Tender

Rs. 2172766.82

Name of The Bidder :-

Contract No :-

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	E/W in excavation of foundation trenches in Laterite rock or any hard rock other than granite removed by chiselling including dressing of sides and levelling the bed not exceeding 1.5m in depth and depositing the soil within initial lead of 50m complete as directed by the Engineer in charge.	41.85	Cum	2356.20	Rupees Two Thousand Three hundred FiftySix & Twenty Paise Only	Rs. 98606.97
2	R.C.C. M20 using 20 mm to 10mm size black hard crusher broken granite stone chips of approved quality and from approved quarry etc. complete in all respect .	124.178	Cum	8204.68	Rupees eight Thousand Two hundred Four & Fifty EightPaise Only	Rs. 1018828.34
3	Rigid & smooth centring and shuttering for R.C.C. work including false work and dismantling then after casting and curing for 21 days including cost & carriage, royalty & taxes etc. of all materials required for the work etc. complete in ground floor as per the specification & direction of Engineer in charge.	95.10	sqm	248.06	Rupees Two hundred FourtyEight & six Paise Only	Rs. 23590.50
4	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars, cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge. ( Weight of binding wire shall not be considered for payment in any shape at all ).	7.15	Qntl	8598.97	Rupees Eight thousand Five hundred Ninty eight & Ninty Seven Paise only	Rs. 61482.63
5	Supplying, fitting and fixing hand railing of Stainless steel of 304 grade using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, cost of all labour, T&P etc. required for the complete in all respect as per direction of the Engineer-in-charge.	273.00	Rmtr	3554.06	Rupees Three thousand Five hundred FiftyFour and six paise only	Rs. 970258.38

TOTAL

Rs. 2172766.82

( Ruppes TwentyOne lakh Seventy Two thousand Seven hundred sixtysix & Eighty Two Paise ) Only

Approved for 05 (Five) Items Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_ pages




Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

  
Asst Engineer  
Bhuban Block

  
Asst/Exe Engineer  
Bhuban Block

  
Block Dev Officer  
Bhuban Block

  
Asst. Engineer  
Zilla Parishad, Dhenkanal

  
Assistant Executive Engineer  
Zillaparisad.Dhenkanal

  
Addl EO(Tech)  
ZillaParishad, Dhenkanal

My/Our Quoted rate is  
above tendered amount of Rs

(both in figure & Words) Excess over/Less than/Equal to the  
Only

Contractor