

## TENDER SCHEDULE

Name of the Work:- Construction of Road from Sainbiri Nuasahi to NH-55  
 Name of the GP:- Gadasila  
 Name of the Scheme:- BGBO- Bikashita Gaon Bikashita Odisha  
 Financial Year:- 2024-25

Name of the Bidder.....

Contact No.....

Sl. No.	Description of items	Unit	Quantity	Rate	Rate in Words	Amount
<b>A</b>	<b>CIVIL WORKS</b>					
1	Earth work in excavation in foundation trenches, column foundation, pit, etc in all kind of soil including moorum stony earth and earth mixed with boulders except sheet rock and boulders not requiring blasting including dressing of sides and levelling the bed up to the required depth and depositing the excavated materials away from the work site with initial lead of 50 mtr and all lifts, including shoring, shuttering & dewatering (if required) with cost of labour, labour cess, hire & running charges of all machineries, sundries & T&P required for the work complete as directed by the Engineer in charge.	cum	16.34	270.90	(Rupees Two hundred Seventy and Ninety Paise Only)	4426.51
2	Supplying and filling with sand in foundation and plinth in layers not exceeding 20 cm in depth, well watered and compacted , top surface dressed and levelled to proper level and gradient including cost of all materials, conveyance, royalties, loading, unloading, cost of all labour, T&P, etc. all complete as per the direction of Engineer-in-Charge.	Cum	82.89	1455.75	(Rupees One Thousand Four Hundred Fifty Five and Seventy Five Paise Only)	120,667.12
3	Providing and lying Plain Cement Concrete of proportion (1:3:6) using 40 mm size grade black hard crusher broken granite stone metal, washed and screened sharp sand of approved quality from approved quarry including hoisting, lowering, laying the concrete, ramming, watering and curing etc. complete to required thickness including cost of all materials, conveyance, loading, unloading, royalties, cost of labours, T&P, hire & running charges of concrete mixer, etc. all complete as per the direction of the Engineer -in -charge.	Cum	110.11	6591.18	(Rupees Six Thousand Five Hundred Ninety One and Eighteen Paise Only)	725,754.83
4	Providing and lying Cement Concrete of proportion (1:2:4) using 12 mm size grade black hard crusher broken granite stone chips washed and screened sharp sand of approved quality from approved quarry including hoisting, lowering, laying the concrete, ramming, watering and curing etc. complete to required thickness including cost of all materials, conveyance, loading, unloading, royalties, cost of labours, T&P, hire & running charges of concrete mixer, etc. all complete as per the direction of the Engineer -in -charge.	Cum	88.33	8236.85	(Rupees Eight Thousand Two Hundred Thirty Six and Eighty Five Paise Only)	727,560.96
5	Rigid smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials and RCC works complete.	sqm	242.00	247.41	(Rupees Two hundred Forty Seven and Forty One Paise Only)	59,873.22

6	Hire & Running charges of Vibrator including all cost of Labour & material.. Etc compl.	Hr	165.77	154.76	(Rupees One Hundred Fifty Four and Seventy Six Paise Only)	25,654.57
TOTAL COST OF WORKS					Rs	1,663,937.21

Rupees Sixteen Lakh Sixty Three thousand Nine hundred Thirty Seven and Twenty One paisa only

Total No. of Pages Enclosed (other than DTCN ) \_\_\_\_\_ Pages

Notes :- The Contractor should not write any thing except quoting of percentage Excess /Less/ Equal to the Estimate up to two decimal points only.

Conditions:- All materials Labour, Machinnaries and Equipments required to complete the work in all respect will be arranged by the tenderer at his own cost. The Employer will bear no responsibility on this aspect.

Conditions:- All materials Labour, Machinnaries and Equipments required to complete the work in all respect will be arranged by the tenderer at his own cost. The Employer will bear no responsibility on this aspect.

The amount put to tender is exclusive of GST. The intending bidder should offer the rates exclusive of GST. GST as applicable on works contract shall be paid over the bill amount at the time of payment of bill.

**N B:- GST,IncomeTax,Royalty,Labour Cess,Additional Charges, EMF, DMF as applicable will be deducted from the bill of the Contractor for all the above works .The Minimum Grade of Cement shall be OPC & HYSD bars of Fe 500.**

  
 21/5/22  
 Block Development Officer  
 Odapada

My / Our quoted rate is of \_\_\_\_\_ (both in figures & words)  
 ) Excess over / Less than the above estimated cost.

**CONTRACTOR**  
(Full Signature)