

TENDER SCHEDULE

NAME OF THE WORK : CONSTRUCTION OF OFFICE BUILDING WITH MARKET COMPLEX OF GPLF IN GARH PALASUNI GP

NAME OF THE GP : GARH PALASUNI

NAME OF THE SCHEME : GPLF / MISSION SHAKTI

TENDER INVITING AUTHORITY : BLOCK DEVELOPMENT OFFICER , KANKADAHAD

CONTRACT NO :

BIDDER NAME :

Amount put to Tender : 2,471,778.05

Sl. No.	Description of Work	Unit	Quantity	Estimated Rate in Rs	Rate in Words	Amount
1	E/W in excavation of foundation trenches in hard soli including dressing of sides and levelling the bed complete as directed by the Engineer in charge.	CuM	112.30	270.90	Rupees Two Hundred seventy & Ninety Paisa only	30,422.07
2	Supplying and filling in foundation trenches and plinth,ditches with sand well watered and rammed etc.complete in all respect as per direction by the Engineer in charge.	CuM	46.68	1215.50	Rupees One Thousand Two Hundred Fifteen & Fifty Paisa only	56,739.54
3	Providing and laying P.C.C (1:3:6) in foundation and floors using 4cm size black hard crusher broken granite stone metal and screened and washed sharp sand for mortar etc complete as per the direction of the Engineer -in-Charge.	CuM	22.46	6996.20	Rupees Six Thousand Nine hundred Ninety Six & Twenty Paisa only	157,134.65
4	Fly Ash brick masonry in cement mortar (1:4)using factory made Fly brick of 10" size etc.complete in all respect as directed by the Engineer-in-charge.					
	Superstructure 5" wall	CuM	3.66	6629.50	Rupees Six thousand Six hundred Twenty Nine & Fifty paisa only	24,263.97
5	Flyash brick masonry in cement mortar(1:6) using kiln Burnt bricks of 10" etc.complete in all all respect as directed by the Engineer-in-charge.					
	A) Foundation and Plinth	CuM	10.55	5950.31	Rupees Five thousand Nine hundred Fifty & Thirty One paisa only	62,775.77
	B) Superstructure	CuM	27.52	5983.60	Rupees Five thousand Nine hundred Eighty Three & Sixty paisa only	164,668.67
6	Back filling of surplus excavated earth at work site by initial lead of 50.00 mtr and initial lift of 1.50 mtr including cost of all labour by Engineer-in -Charge.As per Excavated Earth	CuM	140.21	129.60	Rupees One Hundred Twenty Nine & Sixty Paisa only	18,171.22
7	R.C.C. work of M - 20 grade with 10 mm size black hard crusher broken granite stone chips of approved quality and from approved quarry etc.complete in all respect.					-
i)	Column Footings & Pedestals	CuM	25.16	7542.90	Rupees Seven Thousand Five Hundred Fourty Two & Ninety Paisa only	189,779.36
ii)	Plinth Bands	CuM	9.78	8409.20	Rupees Eight Thousand Four Hundred Nine & Twenty Paisa only	82,241.98
iii)	Columns	CuM	9.65	16685.90	Rupees Sixteen Thousand Six Hundred Eighty Five & Ninety Paisa only	161,018.94

v)	Lintel Bands	CuM	3.29	15156.00	Rupees Fifteen Thousand One Hundred Fifty Six Only	49,863.24
v)	Chajjas	SqM	7.34	1296.70	Rupees One Thousand Two Hundred Ninety Six & Seventy Paise only	9,517.78
vi))	Beam	Cum	10.06	16685.90	Rupees Sixteen Thousand Six Hundred Eighty Five & Ninety Paise only	167,860.15
vii))	Roof Slab	CuM	16.94	14721.70	Rupees Fourteen Thousand Seven Hundred Twenty One & Seventy Paise only	249,385.60
8	straightening,Cutting,Bending bent up or coiled rods,including cracking,hooking,welding or jointing the M.S rods etc.complete as direction by the-in-Charge.	Qtl	70.73	8,532.90	Rupees Eight Thousand five Hundred Thirty Two & Ninety Paise only	603,532.02
9	Providing 12 mm thick C.P with C.M(1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints etc.complete in all respect by the Engineer in charge.	SqM	149.83	197.00	Rupees One Hundred Ninety Seven only	29,516.51
10	Providing 16 mm thick C.P with C.M(1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints etc.complete in all respect by the Engineer in charge.	SqM	319.17	281.80	Rupees Two Hundred Eighty One & Eighty Paise	89,942.11
11	Providing 6 mm thick C.P with C.M(1:4) with screened and washed sharp sand for mortar and finished smooth to R.C.C work after closed deep chipping & slurry treatment including watering and curing, etc.complete in all respect by the Engineer in charge.	SqM	90.16	215.70	Rupees Two Hundred Fifteen & Seventy Paise only	19,447.51
12	Painting two coats with approved weather seal paints of approved colour,shade on wall surface over a coat of wall primer including sand papering,polishing the surface,etc,complete as per specification & direction of Engineer -in -charge.	SqM	149.83	181.00	Rupees One Hundred Eighty One Only	27,119.23
13	Supplying, fitting and fixing of tile in floor marbonite or equivalent make in all floor over 25mm thick bed of cement mortar(1:4) jointed with neat cement slurry mixed with pigment to match the shadees of the tiles etc.complete.as per direction of Engineer-in-charge.	SqM	429.73	188.90	Rupees One Hundred Eighty Eight & Ninety Paise only	81,176.00
14	Painting two coats with approved enamel paint of approved colour,shade over a coat of primer over new iron work including sand papering,polishing the surface,etc,complete as per specification & direction of Engineer-in-charge.	SqM	105.54	267.30	Rupees Two Hundred Sixty Seven &Thirty Paise	28,210.84
15	Supplying, fitting and fixing MS doors and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	KG	1654.13	100.00	Rupees One Hundred Only	165,413.00
16	Labour for fitting and fixing of G.I doors and windows etc.all complete.	SqM	38.34	93.32	Rupees Ninty Three &Thirty Two Paise	3,577.89

	Total					Rs	2,471,778.05
--	--------------	--	--	--	--	-----------	---------------------

**Rupees Twenty Four Lakh Seventy One Thousand
Seven Hundred Seventy Eight & Five Paise only**

Approved for 16 (Twenty-one) Items only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes: The Contractor should not write anything except quoting of percentage, Excess / Less / Equal to Estimate up to two decimal points only.

Conditions: All Materials, Labours, Machineries & Equipments required to complete the work in all respect be arranged by the Tenderer at his own cost.

The Employer will bear no responsibility in this aspect.

N.B. : GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works minimum grade of cement shall be OPC, TMT High Strength Steel Fe 500 Like SAIL/ TISC / Jindal



Assistant Executive Engineer,
Kankadahad Block.



Block Development Officer,
Kankadahad.

My / Our quoted rate is _____ (both in figures & words) Excess over / Less than / Equal to the
above tendered amount of Rs. Only

Contractor