

**GOVERNMENT OF ODISHA**  
**DEPARTMENT OF P.R & D.W**  
**Panchayat Samiti Office, Dhenkanal Sadar**

E-mail: ori-bdhenkanal@nic.in

**SEALED TENDER ENQUIRY NOTICE**

**ID NO:- DHENKANAL/ 2800 /2025-26/ Dt.23.06.2025**

Block Development Officer, Dhenkanal Sadar invites tenders/quotations from reputed agencies / firms with adequate experience and expertise having valid GST No. PAN and IT return of Previous 1 years for "Establishment of Comprehensive Permanent Skill Lab Unit at 6<sup>th</sup> Floor of District Head Quarter Hospital(DHH), Dhenkanal". The interested agencies / firms may furnish their quotation/tender in sealed envelope super scribed "Establishment of Comprehensive Permanent Skill Lab Unit at 6th Floor of District Head Quarter Hospital (DHH), Dhenkanal". The quotations can only be submitted through Registered Post/ Speed Post / Courier/In hand latest by **02/07/2025 5.00 PM** in the Office chamber of the Block Development Officer, Dhenkanal Sadar. The intending bidder needs to submit a non-refundable tender/quotation cost of Rs.2000.00(Rupees. Two Thousand) only in shape of TDR/FDR/NSC duly pledged in favour of BDO, Dhenkanal Sadar. The Authority shall not be responsible for any postal delay about Non-receipt /Non-delivery of the quotations or due to wrong addressee.

The quotations inviting Authority i.e Block Development Officer, Dhenkanal Sadar reserves all the rights to reject or cancel any or all the bids or the entire selection process at any stage without assigning any reason thereof. The purchase/ tender committee reserves the right to call for demonstration of the quality of the materials as and when required. No claim, whatsoever, shall be admissible for the alleged loss / damages suffered by the bidders on account of any such rejections. For detail items & specifications, please visit our website [www.dhenkanal.nic.in](http://www.dhenkanal.nic.in).

Name of Tender/ Quotation	Establishment of Comprehensive Permanent Skill Lab Unit at 6 <sup>th</sup> Floor of District Head Quarter Hospital(DHH) Dhenkanal
Estimated Amount (In Rs.)	48,00,000/- (Including GST)
Period of Completion	1 Month
Time period for supply and Installation of item after Release of purchase order	Within One Month
Quotation Submission Start Date	24.06.2025 1.00 PM
Quotation Submission End Date & Time	2.7.2025 5.00 PM
Quotation Opening Date & Time	2.7.2025, 5.30 PM at Office Chamber of the BDO, Dhenkanal Sadar
Address for submission of Quotation	Panchayat Samiti Office, Dhenkanal Sadar , At/PO/Dist.-Dhenkanal, Odisha-759001

  
Block Development Officer  
Dhenkanal Sadar 23/06/25

**Memo No:2801// Dated . 23.06.2025**

Copy submitted to the Chief Development Officer-cum-Executive Officer, Zilla Parishad Dhenkanal/ Sub-Collector, Dhenkanal for favour of kind information.

  
Block Development Officer  
Dhenkanal Sadar 23/06/25




**Memo No: 2802// Dated . 23.06.2025**

Copy forwarded to All BDOs of Dhenkanal Districts/ All Tahasildars of Dhenkanal Districts/ All CDPOs of Dhenkanal Districts for favour of kind information and necessary action. They are requested display this Tender/ Quotation Call Notice in their office Notice Board for wide publicity.

  
Block Development Officer  
Dhenkanal Sadar


**Memo No: 2803// Dated . 23.06.2025**

Copy to All the Sarpanchs & PEOs under Dhenkanal Block of for favour of kind information and necessary action. They are requested display this Tender/ Quotation Call Notice in their office Notice Board for wide publicity.

  
Block Development Officer  
Dhenkanal Sadar

**Memo No: 2804// Dated . 23.06.2025**

Copy to this Office Notice Board for wide publicity

  
Block Development Officer  
Dhenkanal Sadar

**Memo No: 2805// Dated . 23.06.2025**

Copy Submitted to DIO, NIC Dhenkanal for information and necessary action. He is requested to upload the Tender Call Notice along with the detail specification in Dhenkanal District Website [dhenkanal.odisha.gov.in](http://dhenkanal.odisha.gov.in).

  
Block Development Officer  
Dhenkanal Sadar

**Details of Specifications for Establishment of Comprehensive Permanent Skill Lab Unit at 6th Floor of District Head Quarter Hospital(DHH), Dhenkanal**

Sl. No.	Items	PARTICULARS	UNIT	Specification	QUANTITY	RATE Excluding GST	AMOUNT
1	Flooring	Providing and fixing of raised stepped Flooring. Each step to be 3" elevated in sequence.	Kg	iron pipe(2"/2",2"/1",1"/1")	10752.69		
2		Recessed wiring to light point /Exhaust fan point / Call Bell point with 1.5 sq. mm. FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metalic PVC flexible conduit with 6Amp, 250V Moular switch with ISI marked and ceiling rose ISI mark mounted on metetal box having front modular cover of suitable size, metal box with 1.5 sq mm. FR PVC insulated single core multistrand conductor as earth wire including all accessories and connection.(Make of Wire- Anchor/ Havels/Finolex) (Make of Switch-Legrand /Roama)					
		Light Point Group-A	Each		20	612.00	12240
		Light Point Group-B	Each		33	905.00	29865
		Light Point Group-C	Each		39	1278.00	49842
		Do-fan Point					
		Group-B			6	905.00	5430
		Group-C			6	1278.00	7668
3		Point wiring to 5Amp socket outlet with 2×1.5 sq mm FR PVC insulted single core multistrand cooper conductor of ISI marked in recess 20mm dia non-metalic PVC felxible conduit with piano type switch, phenolic laminated sheet suitable size ISI marked MS box and earthing point with 1× 1.5 sq mm. FRPVC insulated single core multistrand copper conductor for loop earthing etc. as required (Make of Wire- Finolex/ Anchor /Havvels / V-Guard ) ( Make of Switch- Roma /Legrand)					
		Separate Point	Each		4	417.10	1668
4		S/F of 5 Amp plug with switch on exsiting board (Modualr Type)(Roma/ Legrand)	Each		12	144.00	1728

5		Recessed wiring to sub main in the following sq.mm FR PVC insulated single core multi strand copper conductor of ISI marked conforming to IS-694/1990 in 20 mm dia non-metallic heavy duty flexible conduit 1.6 mm thick along with the following sq.mm FR PVC insulated single core multi strand copper conductor as earth wire as required complete in all respect as per direction of Engineer in Charge (Havells/Finolex/anchor)					
a		2 X 1.5 sq.mm +1X1.5 sq.mm 1100 Volts confirming to IS 694/1990	Mtr		135	157.00	21195
b		2 X 2.5 sq.mm +1X1.5 sq.mm 1100 Volts confirming to IS 694/1990	Mtr		219	171.00	37449
c		2 X 4 sq.mm +1X1.5 sq.mm 1100 Volts confirming to IS 694/1990	Mtr		72	188.00	13536
d		2 X 6 sq.mm +1X1.5 sq.mm 1100 Volts confirming to IS 694/1990 in 25 mm dia non-metallic heavy duty flexible conduit	Mtr		62	219.00	13578
		For Inverter wiring 1x1.5 sqmm	Mtr		99	66.00	6534
5	Ceiling Lights Strip Light Fan & Wire	S/F Modular Computer board consisting 3 Nos 5 amp and 1 Nos. 15 Amp switch and Socket (Make of Switch-Roma/Legrand)	Each		2	1490.00	2980
6		S/F AC Point Consisting of 32 Amp DP MCB and stator with all connection complete in all respect as per direction of of Engineer In Charge(Roma/Legrand)	Each		4	1250.00	5000
7		Supply and Fixing of 3A LED flexi strip light 5 Mtr with Driver	Mtr		125	650.00	81250
8		Supply and fixing of recessed fitting 15/18 watt recess mounted pressure die cast aluminium luminaire in powder coated with finish in square profile with optimised heat sink for efficient heat sink for efficient heat dissipation and separate replaceable electronic driver 18W LED 3000K (Phillips/Havells/Crompton)	Each		55	1297.00	71335
9		S/F of A.C Ceiling fan 48 " Size.(Make-Usha/Elora/Crompton decora)			12	2384.00	28608
10		S/F step type Modular Fan Regulator with all connection complete in all respect as per direction of Engineer In Charge(Make- Roma/Legrand)	Each		12	294.00	3528

11	S/F standard Earthing with medium Class 40 mm 3 Mtr Long ISI marked GI Earth pipe Including accessories such as funnel GI nut, Bolt, Washer, hinged cover plate with locking arrangement, 40mm to 20GI radius 5 Nos. 20 mm dia holes on GI pipe required charpol salt, Excavation of earth brick work in cement mortar complete in all respect as per specification of SR 2011 and as per direction of Engineer-in-charge	Each		1	2446.00	2446
12	Providing and fixing of 80 SWG(4mm) dia copper wire on surface or in recess for loop earthing alongwith existing surface / recessed conduit / submain wiring / cable as required	Mtr		18	59.00	1062
13	Supply and fixing of single pole mcb with sheet steel enclosure, distribution board, on surface/recess, complete with tinned copper bus bar, neutral bus bar, earth, din bar, detachable grand plate					
	8 way double door	Each		2	1639	3278
14	supply and fixing of 5 to 32 amp rating 240 volt c series miniature circuit breaker suitable for lighting and other loads of the following poles in the existing MCB DB ISI marked complete with connection testing and commissioning as required.(Make-Legrand/Seimens/schneider / L & T)					
	Single Pole	Each		8	143.00	1144
	32 Amp DP MCB	Each		4	1050.00	4200
15	Supply, Installation , Testing and commissioning of 63 Amp pannel (16 / 18 SWG single door pannel board of size 18"×12"×10') with provision of 1 No. 63 A MCCB, copper busbar 25×5mm 1 no, Micro LED phase Indicator-3 Nos, in all respect as per direction of Engineer-in-Charge (Make-Legrand/Seimens/Schneider/L & T)	Each		1	17798.00	17798
	Projector	Nos.	5000 lumen	1		
	Screen	Nos.	Suvira/Viewsonic-(144 inch-D)	1		
	Motorized projector screen (Digonal-144/150 inch) Audio van					
	Noise Free Operation					
	RF Remote Control with In-Line switch for					
	Wide angle of vision with both GB & MW Fabric					

16

Stand Projector	Ceiling Mount with HDMI (optical fiber cable up to 100Gbps Bandwidth) Cable and Power Cable	Nos.	stand-1+Power cable+HDMI	1		
Steps	Providing of 4 Nos. of steps from door.	SQFT	iron pipe(2"/2",2"/1",1"/1")	16		
Sound System (AHUJA)	wall Mounted Speaker	Nos.	60w	6		
	stage Speaker	Nos.	300W	2		
	Mixer unit	Nos.	6 Chnnel 20Hz to 18 KHz (Frequency) and 220-240 V (Power Supply)	1		
	mic	Nos.	DGN-PA Public Address Senario)	2		
	wireless microphone	Nos.	AWN 630VG	3		
	Active loud speaker	Nos.	Built in 300W RMS Amplifier	2		
			Volume Control, Ground Lift Switch and Phase Reversal switch			
			High Pass Out Put which can be used to drive the top Speaker without external crossover			
	mic cable	Nos.	CC-125M Mic	2		
	2.5mm speakercable	Nos.	2.5mm Tnned Copper	3		
	wall bracket	Nos.	AWB-30	6		
	Installation	Nos.		1		
	people link camera	Nos.	PTZ Camera/Re-1080/10X/Coaxial system (HD analog PTZ Dome)	1		
	audio amplifier (LXA2400)	Nos.	Dual Channel direct coupled amplifier	1		
Class H Operation for optimum efficiency						
		Input Connector =2× XLR, Stero Phone Jack				
		Input Sensitivity =OdBu(775mv)				
3.0 Active	Nos.	ADC Analog RCA L/R-3.5mm	1			
USB cable analog to digital converter with rack for amplifier	Nos.	Converter	1			
17	Carpeting Flooring	Providing and fixing of carpet Flooring Thickness 6 mm covering typically consisting of an upper layer of pile attached to a backing synthetic fibers such as polypropylene nylon, or polyester.	SQFT	6mm thick (D-Décor) brand	1244.44	

18	Cushioned Wall Paneling	Providing and fixing of cushioned wall panelling as per design made with foam, fabric etc.	SQFT	foam-1.5"/Lether of fabric roll	408.21	755.00	308199
19	Auditorium Chair.	Providing and fixing of Auditorium chairs, Push Back, PU Foam, PP Cushion Arm with upholder, fire retardant fabric Tapestry,.(GEEKEN)	Nos.	GEEKEN Chair	70		
20	Wall Paneling	Providing and fixing of wall panelling as per design made with 19mmPly,laminated 1.00mm sunmaica etc.	SQFT	Green PLY/Centuri/Allisan	461.54	650.00	300001
21	Table	Providing and fixing of Table made with ply and laminate	SQFT	1.50x0.60mx0.90	88.89	1125.00	100001
22	Doors	Providing and fixing of 2 Nos. of doors with steel handle having Minimum 3 clamp along with hydrolic door closer.(Excluding Chaukath)	SQFT	3"-Flus Door	60.22		
23	False Ceiling	Providing and fixing of Gypsme Board false ceiling(Saint Gobain False ceiling).	sqm	1/2 Inch	112.58	1893.13	213129
24	Paint	Providing and application of paint(Royal Shine Paint asian) on putty	sqm	Putty	95.82	92.45	8859
		Providing and application of paint (Royal Shine Paint asian)on ceiling.	sqm	Distemper	82.63	113.64	9390

It is to note that the items for which schedule of rate is not available and tender committee has been formed which has suggested market price of the items. The bidder even if L1, if price of any item found to be more than market rate, it will be subjected to further negotiation with the authority failing which authority reserves all the right to cancel the tender/quotation without mentioning any reason there of.

Asst Executive Engineer  
Sadar Block Dhenkanal

Block Development Officer  
Dhenkanal Sadar