

TENDER SCHEDULE

NAME OF THE WORK : CONSTRUCTION OF OFFICE BUILDING WITH MARKET COMPLEX OF GPLF IN MAHABIROD GP

NAME OF THE GP : MAHABIROD

NAME OF THE SCHEME : GPLF / MISSION SHAKTI

TENDER INVITING AUTHORITY : BLOCK DEVELOPMENT OFFICER , KANKADAHAD

CONTRACT NO : .

BIDDER NAME :

Amount put to Tender : 2,472,047.34

Sl. No.	Description of Work	Unit	Quantity	Estimated Rate in Rs	Rate in Words	Amount
1	E/W in excavation of foundation trenches in hard soli including dressing of sides and levelling the bed complete as directed by the Engineer in charge.	CuM	114.83	270.90	Rupees Two Hundred seventy and Ninety Paisa only	31,107.45
2	Supplying and filling in foundation trenches and plinth,ditches with sand well watered and rammed etc.complete in all respect as per direction by the Engineer in charge.	CuM	39.83	1149.70	Rupees One Thousand one Hundred forty nine & Seventy Paisa only	45,792.55
3	Providing and laying P.C.C (1:3:6) in foundation and floors using 4cm size black hard crusher broken granite stone metal and screened and washed sharp sand for mortar etc complete as per the direction of the Engineer - in-Charge.	CuM	20.50	6992.80	Rupees Six Thousand Nine hundred ninety two & Eighty Paisa only	143,352.40
4	Fly Ash brick masonry in cement mortar (1:4)using factory made Fly brick of 10" size etc.complete in all respect as directed by the Engineer-in-charge.					
	Superstructure 5" wall	CuM	3.86	6543.40	Rupees Six thousand five hundred fourty three and forty paia only	25,257.52
5	Flyash brick masonry in cement mortar(1:6) using kiln Burnt bricks of 10" etc.complete in all all respect as directed by the Engineer-in-charge.					
	A) Foundation and Plinth	CuM	10.32	5858.28	Rupees Five thousand Eight hundred fifty Eight and Twenty Eight paia only	60,457.45
	B) Superstructure	CuM	28.66	5891.60	Rupees Five thousand Eight Hundred Ninety one and Sixty paia only	168,853.26
6	Back filling of surplus excavated earth at work site by initial lead of 50.00 mtr and initial lift of 1.50 mtr including cost of all labour by Engineer-in -Charge.As per Excavated Earth	CuM	117.21	129.60	Rupees One Hundred Twenty Nine & Sixty Paisa only	15,190.42
7	R.C.C. work of M - 20 grade with 10 mm size black hard crusher broken granite stone chips of approved quality and from approved quarry etc.complete in all respect.					
i)	Column Footings & Pedestals	CuM	18.61	7563.70	Rupees Seven Thousand Five Hundred Sixty three & Seventy paia only	140,760.46
ii)	Plinth Bands	CuM	9.98	8430.00	Rupees Eight Thousand Four hundred Thirty only	84,131.40
iii)	Columns	CuM	10.59	16706.70	Rupees Sixteen Thousand Seven Hundred Six & Seventy Paisa only	176,923.95

iv)	Lintel Bands	CuM	3.08	15176.80	Rupees Fifteen Thousand One Hundred Seventy six & Eighty Paise only	46,744.54
v)	Chajjas	SqM	6.14	1298.00	Rupees One Thousand Two Hundred Ninty Eight only	7,969.72
vi))	Beam	Cum	10.21	16706.70	Rupees Sixteen Thousand Seven Hundred six & Seventy Paise only	170,575.41
vii))	Roof Slab	CuM	16.94	14742.40	Rupees Fourteen Thousand Seven Hundred Fourty Two & Fourty Paise only	249,736.26
8	Straightening,Cutting,Bending bent up or coiled rods,including cracking,hooking,welding or jointing the M.S roads etc.complete as direction by the-in-Charge.	Qtl	66.45	8,552.25	Rupees Eight Thousand Five Hundred Fifty two & Twenty Five Paise only	568,297.01
9	Providing 12 mm thick C.P with C.M(1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints etc.complete in all respect by the Engineer in charge	SqM	149.83	197.70	Rupees One Hundred Ninety Seven & Seventy Paise only	29,621.39
10	Providing 16 mm thick C.P with C.M(1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints etc.complete in all respect by the Engineer in charge.	SqM	319.17	282.50	Rupees Two Hundred Eighty Two & Fifty paise only	90,165.53
11	Providing 6 mm thick C.P with C.M(1:4) with screened and washed sharp sand for mortar and finished smooth to R.C.C work after closed deep chipping & slurry treatment including watering and curing, etc.complete in all respect by the Engineer in charge.	SqM	30.00	216.40	Rupees Two Hundred Sixteen & Fourty Paise only	6,492.00
12	Supplying, fitting and fixing of tile in floor marbonite or equivalent make in all floor over 25mm thick bed of cement mortar(1:4) jointed with neat cement slurry mixed with pigment to match the shadees of the tiles etc.complete.as per direction of Engineer-in-charge.	SqM	74.99	1163.70	Rupees One Thousand One Hundred Sixty Three & Seventy paise only	87,265.86
13	Supplying, fitting and fixing of tile in dadoo marbonite or equivalent make in all floor over 25mm thick bed of cement mortar(1:3) jointed with neat cement slurry mixed with pigment to match the shadees of the tiles etc.complete.as per direction of Engineer-in-charge.	SqM	7.45	1295.40	Rupees One Thousand Two Hundred Ninety Five & Fourty Paise only	9,650.73
14	Painting two coats with approved weather seal paints of approved colour,shade on wall surface over a coat of wall primer including sand papering,polishing the surface,etc,complete as per specification & direction of Engineer -in -charge.	SqM	149.83	181.00	Rupees One Hundred Eighty One only	27,119.23
15	Painting 2 coats with Plastic emulsion paint over a coat of water bond cement primer to make an even finished surface in all floors and heights to make an even finished surface in all floors and heights to wall surface of approved make and shade including sand papering,applying putty wherever necessary & cost of scaffolding,staging charges with cost,conveyance,taxes of all materials,cost of all labour,T&P etc.complete as per direction of the Engineer-in-charge.	SqM	402.45	188.90	Rupees One Hundred Eighty Eight & Ninety Paise only	76,022.81

16	Painting two coats with approved enamel paint of approved colour, shade over a coat of primer over new iron work including sand papering, polishing the surface, etc, complete as per specification & direction of Engineer-in-charge.	SqM	105.54	267.30	Rupees Two Thousand Sixty Seven & Thirty Paise only	28,210.84
17	Supplying, fitting and fixing MS doors and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	Kg	1654.13	100.00	Rupees One Hundred only	165,413.00
18	Labour for fitting and Fixing of G.I doors, window gates as per approved desing including fixing of door and windows clamps with CC(1:3:6) using 12mm size hbg chips and curing 7 days after fixing the clamps including cost, conveyance, royalty, taxes etc complete.	Kg	38.34	93.32	Rupees Ninety Three & Thirty Two Paise only	3,577.89
19	Supplying, fitting, fixing of PVC Door with frame and all fittings including all cost, taxes labour charges etc .complete.	SqM	3.90	1955.90	Rupees One Thousand Nine Hundred Fifty Five & Ninety Paise only	7,628.01
20	Providing, fitting, fixing of 5mm thick plane glass including cost of labour charges & cost of scaffolding & cost of putty etc. complete.	SqM	6.48	884.30	Rupees Eight Hundred Eighty Four & Thirty Paise	5,730.26
Total						Rs 2,472,047.34

Rupees Twenty Four Lakh Seventy Two Thousand Fourty Seven & Thirty Four Paise

Approved for 20 (Twenty-one) Items only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes: The Contractor should not write anything except quoting of percentage, Excess / Less / Equal to Estimate up to two decimal points only.

Conditions : All Materials, Labours, Machineries & Equipments required to complete the work in all respect be arranged by the Tenderer at his own cost.
The Employer will bear no responsibility in this aspect.

N.B. : GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works minimum grade of cement shall be OPC, TMT High Strength Steel Fe 500 Like SAIL/ TISC / Jindal


Assistant Executive Engineer,
Kankadahad Block.


Block Development Officer,
Kankadahad.

My / Our quoted rate is _____
above tendered amount of Rs.

Contractor