

## TENDER SCHEDULE

NAME OF THE WORK : CONSTRUCTION OF OFFICE BUILDING WITH MARKET COMPLEX OF GPLF IN BAAM GP

NAME OF THE GP : BAAM

NAME OF THE SCHEME : GPLF / MISSION SHAKTI

TENDER INVITING AUTHORITY : BLOCK DEVELOPMENT OFFICER , KANKADAHAD

CONTRACT NO :

BIDDER NAME :

Sl. No.	Description of Work	Unit	Quantity	Estimated Rate in Rs	Amount put to Tender : 2,475,644.22	
					Rate in Words	Amount
1	Earth work in hard soil within 50m. initial lead and 1.5m. Initial lift including rough dressing and breaking the clods to maximum 5cm. To 7cm. Laying the layers not exceeding 0.30m. In depth etc complete.	CuM	143.89	270.90	Rupees Two Hundred seventy and Ninety Paise only	38,979.80
2	Providing and filling clean dry sand of approved quality from approved quarry in foundation and plinth in 6" thick layer well watered and rammed incl. cost, conveyance, royalties and taxes of all materials etc.	CuM	47.02	1149.70	Rupees One Thousand one Hundred forty nine & Seventy Paise only	54,058.89
3	C.C.(1:3:6) using 40mm HG metal of approved quality from approved quarry incl. hoisting, compacting curing, finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials, cost of labour and T&p etc. all complete as per the direction of E.I.C.	CuM	26.65	6965.30	Rupees Six Thousand Nine hundred sixty five & Thirty Paise only	185,625.25
4	Flyash brick masonry in C.M. (1:4) using brick of size 25cmx12cmx 8cm of crushing strength not less than 75kg/cm <sup>2</sup> with dimensional tolerance plus minus 8% after immersing the bricks for six hours before use incl. lowering, placing in position, watering and curing and cost, complete.					
	Superstructure 5" wall	CuM	3.66	6531.30	Rupees Six thousand five hundred thirty one and thirty paise	23,904.56
5	Flyash brick masonry in C.M. (1:6) using brick of size 23cmx11cmx 8cm of crushing strength not less than 75kg/cm <sup>2</sup> with dimensional tolerance plus minus 8% after immersing the bricks for six hours before use incl. lowering, placing in position, watering and curing and cost, conveyance, royalties and taxes of all materials, cost of labour & T&P etc. complete as per the direction of E.I.C.(For foundation & plinth). etc all complete.					
A)	Foundation and Plinth	CuM	10.62	5850.21	Rupees Five thousand eight hundred fifty and Twenty one paise	62,129.23

	B)	Superstructure	CuM	27.52	5883.50	Rupees Five thousand eight hundred eighty three and fifty paisa	161,913.92
6		Filling in foundation and plinth with excavated materials including water and ramming as directed by the Engineer-in -charge.	CuM	143.89	129.60	Rupees One Hundred Twenty Nine & Sixty Paisa only	18,648.14
7		R.C.C. work of M - 20 grade with 20 mm and down grade HGCB chips incl. hoisting, laying concrete in layers not exc. 15cm thick, compacting by means of vibrator, curing, finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials, cost of labour and T&p etc. all complete as per the direction of E.I.C.					
i)		Column Footings & Pedestals	CuM	27.37	7522.00	Rupees Seven Thousand Five Hundred Twenty two only	205,877.14
ii)		Plinth Bands	CuM	10.01	8388.30	Rupees Eight Thousand Three Hundred Eighty Eight & Thirty Paisa only	83,966.88
iii)		Columns	CuM	9.21	16664.90	Rupees Sixteen Thousand Six Hundred Sixty Four & Ninety Paisa only	153,483.73
iv)		Lintel Bands	CuM	3.29	15135.00	Rupees Fifteen Thousand One Hundred Thirty Five only	49,794.15
v)		Chajjas	SqM	7.34	1295.30	Rupees One Thousand Two Hundred Ninety Five & Thirty Paisa only	9,507.50
vi))		Beam	Cum	10.29	16664.90	Rupees Sixteen Thousand Six Hundred Sixty Four & Ninety Paisa	171,481.82
vii))		Roof Slab	CuM	16.54	14700.70	Rupees Fourteen Thousand Seven Hundred & Seventy Paisa only	243,149.58
8		Cutting, straightening, coiled or bent up T. S. rod for R.C.C. work incl. bending, binding & tying the grills and placing in proper position with cost, conveyance, taxes of binding wire 18 to 20 gauge and T.S. rod, cost of all labour & T&P etc complete as per the direction of E.I.C.	Qtl	74.48	8,550.49	Rupees Eight Thousand five Hundred fifty & forty Nine Paisa only	636,840.50
9		Supplying, fitting and fixing MS doors and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	KG	1654.13	100.00	Rupees One hundred only	165,413.00
10		Labour for fitting and fixing doors and windows etc.all complete.	SqM	38.34	93.32	Rupees Ninety Three& Thirty Two Paisa only	3,577.89
11		6mm thick cement plaster (1:4), finished smooth to R.C.C. surfaces after cleaning the surface incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	132.00	215.90	Rupees Two Hundred Fifteen & Ninety Paisa only	28,498.80

	16mm thick cement plaster (1:6), finished smooth to brick masonry work in inside surface after cleaning the surface incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	319.17	282.00	Rupees Two Hundred Eighty Two only	90,005.94
13	12mm thick cement plaster (1:6) for brick masonry work in outside surface after racking out joints incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	149.83	197.30	Rupees One Hundred Ninety Seven & Thirty Paise only	29,561.46
14	Painting 2 coats with Plastic emulsion paint over a coat of primer to make an even finished surface.....etc complete	SqM	170.00	188.89	Rupees One Hundred Eighty Eight & Eighty Nine Paise only	32,111.30
15	Weather coat painting two coats with approved shade over a coat of oil bound primer incl. cost of all material, T&P and labour etc complete.	SqM	149.83	180.97	Rupees One Hundred Eighty & Ninety Seven Paise only	27,114.74
	<b>Total</b>					<b>Rs 2,475,644.22</b>

**Rupees Twenty Four Lakh Seventy Five Thousand Six Hundred Forty Four & Twenty Two Paise only**

Approved for 15 ( Fifteen ) Items only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_ pages.

Notes: The Contractor should not write anything except quoting of percentage, Excess / Less / Equal to Estimate up to two decimal points only.

Conditions: All Materials, Labours, Machineries & Equipments required to complete the work in all respect be arranged by the Tenderer at his own cost.

The Employer will bear no responsibility in this aspect.

I.B. : GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works minimum grade of cement shall be OPC, TMT High Strength Steel Fe 500 Like SAIL/ TISC / Jindal



Assistant Executive Engineer ,  
Kankadahad Block.



Block Development Officer ,  
Kankadahad.

My / Our quoted rate is \_\_\_\_\_

above tendered amount of Rs. ....

**Contractor**