

TENDER SCHEDULE

NAME OF THE WORK : CONSTRUCTION OF OFFICE BUILDING WITH MARKET COMPLEX OF GPLF IN KARAGOLA GP

NAME OF THE GP : KARAGOLA

NAME OF THE SCHEME : GPLF / MISSION SHAKTI

TENDER INVITING AUTHORITY : BLOCK DEVELOPMENT OFFICER , KANKADAHAD

CONTRACT NO :

BIDDER NAME :

Amount put to Tender : 2,470,287.37

Sl. No.	Description of Work	Unit	Quantity	Estimated Rate in Rs	Rate in Words	Amount
1	E/W in excavation of foundation trenches in hard soli including dressing of sides and levelling the bed complete as directed by the Engineer in charge.	CuM	88.03	270.90	Rupees Two Hundred seventy and Ninety Paise only	23,847.33
2	Supplying and filling in foundation trenches and plinth,ditches with sand well watered and rammed etc complete in all respect as per direction by the Engineer in charge.	CuM	42.57	1149.70	Rupees One Thousand one Hundred forty nine & Seventy Paise only	48,942.73
3	Providing and laying P.C.C (1:3:6) in foundation and floors using 4cm size black hard crusher broken granite stone metal and screened and washed sharp sand for mortar etc complete as per the direction of the Engineer -in-Charge.	CuM	20.85	6992.80	Rupees Six Thousand Nine hundred Ninety Two & Eighty Paise only	145,799.88
4	Fly Ash brick masonry in cement mortar (1:4)using factory made Fly brick of 10" size etc complete in all respect as directed by the Engineer-in-charge.					
	Superstructure 5" wall	CuM	3.86	6543.40	Rupees Six thousand five hundred Fourty Three & Fourty paise only	25,257.52
5	Flyash brick masonry in cement mortar(1:6) using kiln Burnt bricks of 10" etc.complete in all all respect as directed by the Engineer-in-charge.					
	A) Foundation and Plinth	CuM	10.32	5858.28	Rupees Five Thousand Eight Hundred fifty Eight & Twenty Eight paise only	60,457.45
	B) Superstructure	CuM	28.41	5891.60	Rupees Five thousand eight hundred Ninety One & Sixty paise only	167,380.36
6	Back filling of surplus excavated earth at work site by initial lead of 50.00 mtr and initial lift of 1.50 mtr including cost of all labour by Engineer-in -Charge.As per Excavated Earth	CuM	88.03	129.60	Rupees One Hundred Twenty Nine & Sixty Paise only	11,408.69
7	R.C.C. work of M - 20 grade with 10 mm size black hard crusher broken granite stone chips of approved quality and from approved quarry etc.complete in all respect.					
i)	Column Footings & Pedestals	CuM	22.63	7563.70	Rupees Seven Thousand Five Hundred Sixty Three & Seventy Paise	171,166.53
ii)	Plinth Bands	CuM	9.21	8430.00	Rupees Eight Thousand Four Hundred Thirty Paise only	77,640.30
iii)	Columns	CuM	11.09	16706.70	Rupees Sixteen Thousand Seven Hundred Six & Seventy Paise only	185,277.30
iv)	Lintel Bands	CuM	3.33	15176.80	Rupees Fifteen Thousand One Hundred Seventy Six & Eighty Paise	50,538.74
v)	Chajjas	SqM	7.34	1298.00	Rupees One Thousand Two Hundred Ninety Eighty only	9,527.32
vi)	Beam	Cum	10.28	16706.70	Rupees Sixteen Thousand Seven Hundred Six & Seventy Paise only	171,744.88
vii)	Roof Slab	CuM	16.29	14742.40	Rupees Fourteen Thousand Seven Hundred Fourty Two & Fourty Paise only	240,153.70
8	Straightening,Cutting,Bending bent up or coiled rods,including cracking,hooking,welding or jointing the M.S rods etc.complete as direction by the-in-Charge.	Qtl	67.27	8,598.80	Rupees Eight Thousand five Hundred Ninety Eight & Eighty Paise only	578,441.28
9	Providing 12 mm thick C.P with C.M(1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints etc.complete in all respect by the Engineer in charge.	SqM	149.83	197.70	Rupees One Hundred Ninety Seven & Seventy Paise only	29,621.39
10	Providing 16 mm thick C.P with C.M(1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints etc.complete in all respect by the Engineer in charge.	SqM	319.17	282.50	Rupees Two Hundred Eighty Two & Fifty Paise only	90,165.53

11	Providing 6 mm thick C.P with C.M(1:4) with screened and washed sharp sand for mortar and finished smooth to R.C.C work after closed deep chipping & slurry treatment including watering and curing, etc. complete in all respect by the Engineer in charge.	SqM	30.00	216.40	Rupees Two Hundred Sixteen & Fourty Paise only	6,492.00
12	Supplying, fitting and fixing of tile in floor marbonite or equivalent make in all floor over 25mm thick bed of cement mortar(1:4) jointed with neat cement slurry mixed with pigment to match the shades of the tiles etc. complete.as per direction of Engineer-in-charge.	SqM	49.34	1163.66	Rupees One Thousand One Hundred Sixty Three & Sixty Six Paise only	57,414.98
	Ceramic wall tile	SqM	23.71	1009.80	Rupees One Thousand Nine & Eighty Paise only	23,942.36
13	Painting two coats with approved weather seal paints of approved colour,shade on wall surface over a coat of wall primer including sand papering,polishing the surface,etc,complete as per specification & direction of Engineer -in -charge.	SqM	149.83	181.00	Rupees One Hundred Eighty One Only	27,119.23
14	Painting 2 coats with Plastic emulsion paint over a coat of water bond cement primer to make an even finished surface in all floors and heights to make an even finished surface in all floors and heights to wall surface of approved make and shade including sand papering,applying putty wherever necessary &cost of scaffolding,staging charges with cost,conveyance,taxes of all materials, cost of all labour,T&P etc. complete as per direction of the Engineer-in-charge.	SqM	318.57	188.90	Rupees One Hundred Eighty Eight & Ninety Paise only	60,177.87
15	Painting two coats with approved enamel paint of approved colour,shade over a coat of primer over new iron work including sand papering,polishing the surface,etc,complete as per specification & direction of Engineer-in-charge.	SqM	105.54	267.30	Rupees Two Hundred Sixty Seven &Thirty Paise	28,210.84
16	Supplying, fitting and fixing MS doors and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	KG	1626.23	100.00	Rupees One Hundred Only	162,623.00
17	Labour for fitting and Fixing of G.I doors,window gates as per approved desing including fixing of door and windows clamps with CC(1:3:6) using 12mm size hbg chips and curing 7 days after fixing the clamps including cost,conveyance,royalty,taxes etc complete.	SqM	38.34	93.32	Rupees Ninty Three &Thirty Two Paise	3,577.89
18	Supplying,fitting,fixing of PVC Door with farne and all fittings including all cost,taxes labour charges etc .complete	SqM	3.90	1955.90	Rupees One Thousand Nine Hundred Fifty Five &Ninety Paise	7,628.01
19	Providing,fitting,fixing of 5mm thick plane glass including cost of labour charges &cost of scaffolding & cost of putty etc.complete.	SqM	6.48	884.30	Rupees Eight Hundred Eighty Four &Thirty Paise	5,730.26
Total					Rs	2,470,287.37

Rupees Twenty four Lakh Seventy Thousand Two Hundred Eighty Seven & Thirty Seven Paise only

Approved for 19 (Twenty-one) Items only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes: The Contractor should not write anything except quoting of percentage, Excess / Less / Equal to Estimate up to two decimal points only.

Conditions: All Materials, Labours, Machinaries & Equipments required to complete the work in all respect be arranged by the Tenderer at his own cost.

The Employer will bear no responsibility in this aspect.

N.B.: GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works minimum grade of cement shall be OPC, TMT High Strength Steel Fe 500 Like SAIL/ TISC / Jindal


Assistant Executive Engineer,
Kankadahad Block.


Block Development Officer,
Kankadahad.

My / Our quoted rate is

(both in figures & words) Excess over / Less than / Equal to the above tendered amount of Rs. Only

Contractor