

TENDER SCHEDULE

NAME OF THE WORK : CONSTRUCTION OF OFFICE BUILDING WITH MARKET COMPLEX OF GPLF IN PANGATIRA GP

NAME OF THE GP : PANGATIRA

NAME OF THE SCHEME : GPLF / MISSION SHAKTI

TENDER INVITING AUTHORITY : BLOCK DEVELOPMENT OFFICER , KANKADAHAD

CONTRACT NO :

BIDDER NAME :

Amount put to Tender : 2,471,818.70

Sl. No.	Description of Work	Unit	Quantity	Estimated Rate in Rs	Rate in Words	Amount
1	Earth work in hard soil withen 50m. initial lead and 1.5m. Initial lift including rough dressing and breaking the clods to maximum 5cm. To 7cm. Laying the layers not exceeding 0.30m. In depth etc complete.	CuM	118.96	270.90	Rupees Two Hundred seventy and Ninety Paise only	32,226.26
2	Providing and filling clean dry sand of approved quality from approved quarry in foundation and plinth in 6" thick layer well watered and rammed incl. cost, conveyance, royalties and taxes of all materials etc.	CuM	44.62	1149.70	Rupees One Thousand One Hundred Forty Nine & Seventy Paise only	51,299.61
3	C.C.(1:3:6) using 40mm HG metal of approved quality from approved quarry incl. hoisting, compacting curing, finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials, cost of labour and T&p etc. all complete as per the direction of E.I.C.	CuM	24.26	6965.30	Rupees Six Thousand Nine hundred sixty five & Thirty Paise only	168,978.18
4	Flyash brick masonry in C.M. (1:4) using brick of size 25cmx12cmx 8cm of crushing strength not less than 75kg/cm ² with dimentional tolerance plus minus 8% after immersing the bricks for six hours befour use incl.lowering, placing in position, watering and curing and cost, complete.					-
	Superstructure 5" wall	CuM	3.66	6531.30	Rupees Six thousand five hundred thirty one and thirty paise	23,904.56
5	Flyash brick masonry in C.M. (1:6) using brick of size 23cmx11cmx 8cm of crushing strength not less than 75kg/cm ² with dimentional tolerance plus minus 8% after immersing the bricks for six hours befour use incl.lowering, placing in position, watering and curing and cost, conveyance, royalties and taxes of all materials, cost of labour & T&P etc. complete as per the direction of E.I.C.(For foundation & plinth). etc all complete.					-
	A) Foundation and Plinth	CuM	10.62	5850.21	Rupees Five thousand eight hundred fifty and Twenty one paise	62,129.23
	B) Superstructure	CuM	27.52	5883.50	Rupees Five thousand eight hundred eighty three and fifty paise	161,913.92

6	Filling in foundation and plinth with excavated materials including water and ramming as directed by the Engineer-in-charge.	CuM	79.31	129.60	Rupees One Hundred Twenty Nine & Sixty Paise only	10,278.58
7	R.C.C. work of M - 20 grade with 20 mm and down grade HGCB chips incl. hoisting, laying concrete in layers not exc. 15cm thick, compacting by means of vibrator, curing, finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials, cost of labour and T&p etc. all complete as per the direction of E.I.C.					-
i)	Column Footings & Pedestals	CuM	24.11	7522.00	Rupees Seven Thousand Five Hundred Twenty two only	181,355.42
ii)	Plinth Bands	CuM	10.01	8388.30	Rupees Eight Thousand Three Hundred Eighty Eight & Thirty Paise only	83,966.88
iii)	Columns	CuM	9.21	16664.90	Rupees Sixteen Thousand Six Hundred Sixty Four & Ninety Paise only	153,483.73
iv)	Lintel Bands	CuM	3.29	15135.00	Rupees Fifteen Thousand One Hundred Thirty Five only	49,794.15
v)	Chajjas	SqM	7.34	1295.30	Rupees One Thousand Two Hundred Ninety Five & Thirty Paise only	9,507.50
vi))	Beam	Cum	10.40	16664.90	Rupees Sixteen Thousand Six Hundred Sixty Four & Ninety Paise only	173,314.96
vii))	Roof Slab	CuM	16.54	14700.70	Rupees Fourteen Thousand Seven Hundred & Seventy Paise only	243,149.58
8	Cutting, straightening, coiled or bent up T. S. rod for R.C.C. work incl. bending, binding & tying the grills and placing in proper position with cost, conveyance, taxes of binding wire 18 to 20 gauge and T.S. rod, cost of all labour & T&P etc complete as per the direction of E.I.C.	Qtl	71.36	8,550.49	Rupees Eight Thousand five Hundred fifty & forty Nine Paise only	610,162.97
9	Supplying, fitting and fixing MS doors and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	KG	1682.03	100.00	Rupees One hundred only	168,203.00
10	Labour for fitting and fixing doors and windows etc.all complete.	SqM	38.34	93.32	Rupees Ninety Three & Thirty Two Paise only	3,577.89
11	6mm thick cement plaster (1:4), finished smooth to R.C.C. surfaces after cleaning the surface incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	132.00	215.90	Rupees Two Hundred Fifteen & Ninety Paise only	28,498.80
12	16mm thick cement plaster (1:6), finished smooth to brick masonry work in inside surface after cleaning the surface incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	319.17	282.00	Rupees Two Hundred Eighty Two only	90,005.94

13	12mm thick cement plaster (1:6) for brick masonry work in outside surface after racking out joints incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	149.83	197.30	Rupees One Hundred Ninety Seven & Thirty Paise only	29,561.46
14	Painting 2 coats with Plastic emulsion paint over a coat of primer to make an even finished surface.....etc complete	SqM	429.73	188.90	Rupees One Hundred Eighty Eight & Ninety Paise only	81,176.00
15	Weather coat painting two coats with approved shade over a coat of oil bound primer incl. cost of all material, T&P and labour etc complete.	SqM	149.83	181.00	Rupees One Hundred Eighty One only	27,119.23
16	Painting two coats with approved enamel paints of approved colour, shade over a coat of primer over new iron work including polishing the surface etc.	SqM	105.54	267.30	Rupees Two Hundred Sixty Seven & Thirty Paise	28,210.84
Total						Rs 2,471,818.70

Rupees Twenty Four Lakh Seventy One Thousand Eight Hundred Eighteen & Seventy Paise only

Approved for 16 (Sixteen) Items only


Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes: The Contractor should not write anything except quoting of percentage, Excess / Less / Equal to Estimate up to two decimal points only.

Conditions : All Materials, Labours, Machinaries & Equipments required to complete the work in all respect be arranged by the Tenderer at his own cost.

The Employer will bear no responsibility in this aspect.

N.B. : GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works minimum grade of cement shall be OPC, TMT High Strength Steel Fe 500 Like SAIL/ TISC / Jindal


Assistant Executive Engineer,
Kankadahad Block.


Block Development Officer,
Kankadahad.

My / Our quoted rate is _____
above tendered amount of Rs.

Contractor