

GOVERNMENT OF ODISHA
INVITATION FOR BIDS (IFB)
 Identification No.01/ BDO Parjang
TENDER CALL NOTICE NO. 01 OF 2025-26

E-mail : ori-Parjang@nic.in

1. Block Development Officer, Parjang on behalf of Governor of Odisha invites percentage rate bids for the works (civil only) as detailed in the table from class of contractors mentioned in Col.-4 below registered with the State Government and contractors of equivalent grade / class registered with Central Government / MES / Railways to be eventually drawn up in PWD F-2 (Now P-1) form for execution of civil works, on production of definite proof from the appropriate authority. But successful bidder of other State / MES / Railway / CPWD in equivalent rank has to register under the State PWD before signing the agreement. The bidders may submit bid for the work.

Sl. No.	Name of the work.	Approximate value of work	Class of contractor	Place of receipt of tender papers through Post only.	Cost of BID documents (Non-refundable (Rs.))	EMD 1 %	Period of completion in months
1	2	3	4	5	6	7	8
1	Construction of Grama Panchayat Level Federation Office Building with Market Complex at Roda GP of Parjang Block	Rs.24,48,427.80	B & C Class	BDO, Parjang	Rs.6,000	Rs 24484.00	6 (Six Calendar Month)
2	Construction of Grama Panchayat Level Federation Office Building with Market Complex at Pitiri GP of Parjang Block	Rs.24,34,248.61	B & C Class	BDO, Parjang	Rs.6,000	Rs 24342.00	6 (Six Calendar Month)
3	Construction of Grama Panchayat Level Federation Office Building with Market Complex at Muktapasi GP of Parjang Block	Rs.24,56,208.96	B & C Class	BDO, Parjang	Rs.6,000	Rs 24562.00	6 (Six Calendar Month)
4	Construction of Grama Panchayat Level Federation Office Building with Market Complex at Barihapur GP of Parjang Block	Rs.24,47,837.78	B & C Class	BDO, Parjang	Rs.6,000	Rs 24478.00	6 (Six Calendar Month)

2. Tender documents consisting of specification & schedule of quantities (BOQ) and the set of terms and conditions of contract (DTCN) along with other necessary documents can be obtained/downloaded from district NIC website (www.dhenkanal.odisha.gov.in) from **Dt. 20.06.2025 10.00 AM to 04.07.2025 till 5.00 p.m.** Interested bidders may obtain further information at the address mentioned in Col.5 above.

3. Sealed Bids must be enclosed with appropriate paper cost in shape of a **non-refundable Demand Draft, separately issued in favour of Block Development Officer Parjang & payable at Parjang**
4. **The Earnest Money Deposit (EMD) will be 1 % of the Tender value and should be deposited in shape TDR, FDR, NSC, KVP or small saving deposit from any Nationalized Bank duly pledged in favour of "Block Development Officer", Parjang payable at Parjang at the time of Bidding.**
5. The receipt of the bid documents will start from **Dt. 20.06.2025 at 10.00 AM to 05.07.2025 till 5.00 p. m only through Registered Post/ Speed Post addressed to The Block Development Officer Parjang, Dist. - Dhenkanal, Odisha, PIN – 759120. Delay due to postal will not be considered at any cost.**
6. The bids will be opened on **Dt-08-07-2025 at 11.30 AM** in the office of the under signed in the presence of the bidders or their authorized persons who wish to attend. If the office happens to be closed on the opening day, the bids will be opened on the next working day at the same time and venue accordingly.
7. Bidding documents will be available in the District website i.e. Dhenkanal.nic.in and the same can be downloaded and submitted along with the relevant documents duly filled up and the same can be submitted to **The Block Development Officer Parjang by Registered Post/ Speed post within the stipulated time mentioned above and the Authority will not be held responsible for any kind of postal delay (dispatching Bid documents/receiving sealed Bids), if any.**
8. Sealed Bids should be accompanied with the attested true copies of the valid registration certificate, GSTIN, PAN card, Affidavit and other documents as per DTCN which are mandatory and the original documents submitted by the successful bidder will be verified within five working days of opening of the tender before Block Development Officer Parjang for verification otherwise his / her bids shall be declared as non-responsive and thus liable for rejection and the bidder will be as Black Listed for 2 years from the Department and the EMD amount will be forfeited. The same tender will be rendered further.
9. Other details can be seen in the bidding documents.
10. The enclosures other than the D.T.C.N. should be page numbered and signed by the contractor.
11. Total No. of enclosures should be submitted by him / her in Numbers and words as per relevant clause of D.T.C.N.
12. The authority reserves the right to reject any or all tenders without assigning any reason thereof.
13. The Bid Documents can be downloaded from the Dhenkanal Portal i.e. [www,Dhenkanal.nic.in](http://www.Dhenkanal.nic.in).


 Block Development Officer
 Parjang

Memo No. 3083 Dt- 16/6/25

Copy submitted to the Collector & District Magistrate, Dhenkanal / CDO-Cum-EO, ZP, Dhenkanal / Sub-Collector, Kamakshyanagar with a request to display the above notice in the office Notice Board for wide circulation.


 Block Development Officer
 Parjang

Memo No. 3084 Dt. 16/6/25

Copy to the D.I.O, Dhenkanal for information & necessary action. One copy of this notice & other tender documents (DTCN & BOQ) may be hoisted in the district website for wide circulation.

13/6/25
Block Development Officer
Parjang

Memo No. 3085 Dt. 16/6/25

Copy to the Director, Information & Public Relation Department, ~~Parjang~~ *Bhubaneswar* for publishing of Tender Notice in two Odia & One English daily News Paper for wide circulation.

12/6/25
Block Development Officer
Parjang

Memo No. 3086 Dt. 16/6/25

Copy to Accounts Section/ RSO/ Cashier/ Office Notice Board of this office for kind information.

13/6/25
Block Development Officer
Parjang

Original

BILL OF QUANTITY

NAME OF WORK:-

Construction of Gram Panchayat Level Federation Office Building with**Market Complex at Roda GP of Parjang Block**

AMOUNT PUT TO TENDER :- Rs 2448427.80

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Earth work in excavation of foundation trenches in HARD soil up to the required depth including dressing and leveling the bed and depositing the excavated materials away from the site with all leads and lifts, T&P labour required for the work etc. complete as directed by the Engineer-In Charge.	87.94	Cum	270.90	Rupees Two Hundred Seventy and Ninety Paise	23822.95
2	Cement concrete (1:3:6) in foundation and plinth using 4 cm. size hard granite crusher broken metal of approved quarry and approved quality including hoisting lowering laying concrete in layers not exceeding 0.15 M. in depth including compacting watering and curing etc. complete including cost, conveyance, royalties & of all materials and cost of labour etc with T&P required for the work etc. complete as per specification & direction of Engineer-In-Charge.	21.99	Cum	6923.86	Rupees Six Thousand Nine Hundred Twenty Three and Eighty Six Paise	152255.68
3	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Foundation & Plinth including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	12.44	Cum	5803.97	Rupees Five Thousand Eight Hundred Three and Ninety Seven Paise	72201.39
4	Supplying and filling in foundation and plinth with excavated earth including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	60.20	Cum	150.50	Rupees One Hundred Fifty and Fifty Paise	9060.10
5	Supplying and filling in foundation and plinth with sand including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	32.76	Cum	1436.56	Rupees One Thousand Four Hundred Thirty Six and Fifty Six Paise	47061.71
6	RCC Work M - 20 using 20mm.& down graded black hard crusher broken granite stone chips including hoisting lowering laying and compact concrete by using vibrator watering and curing for 28 days centering shuttering and finishing the exposed surface smooth providing grooves or beads where necessary including cost, conveyance, royalties of all materials and labour with T&P required for the work etc. complete in all respect as per specification & direction of E.I.C					
	A) COLUMN BASE & FOOTINGS	25.19	Cum	7477.57	Rupees Seven Thousand Four Hundred Seventy Seven and Fifty Seven Paise	188359.99

	B) PLINTH BEAM	8.20	Cum	8349.49	Rupees Eight Thousand Three Hundred Forty Nine and Forty Nine Paise	68465.82
	C) COLUMN & BEAM	11.25	Cum	16618.13	Rupees Sixteen Thousand Six Hundred Eighteen and Thirteen Paise	186953.96
	D) LINTEL BAND	3.00	Cum	15088.09	Rupees Fifteen Thousand Eighty Eight and Nine Paise	45264.27
	E) CHAJJA	10.62	Sqm	1274.49	Rupees One Thousand Two Hundred Seventy Four and Forty Nine Paise	13535.08
	F) ROOF SLAB	15.45	Cum	14653.89	Rupees Fourteen Thousand Six Hundred Fifty Three and Eighty Nine Paise	226402.60
7	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	30.33	Cum	5836.97	Rupees Five Thousand Eight Hundred Thirty Six and Ninety Seven Paise	177035.80
8	Fly ash Brick masonry in cement mortar (1:4) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	4.19	Cum	6083.80	Rupees Six Thousand Eighty Three and Eighty Paise	25491.12
9	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars , cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge. (Weight of binding wire shall not be considered for payment in any shape at all).	56.28	Qntl	8522.36	Rupees Eight Thousand Five Hundred Twenty Two and Thirty Six Paise	479638.42
10	Providing & laying 25mm grading concrete (1:2:2) on roof slab using 6mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	125.61	Sqm	414.20	Rupees Four Hundred Fourteen and Twenty Paise	52027.66
11	Supplying MS door & window shutter with grills (Framed&Fixed) made out of MS angles, flats and sheets etc of approved design & fabrication including cost, conveyance & taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	1342.50	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	113776.88

	Labour for fitting and fixing of GI doors, windows and gates as per approved design including fixing of door and windows clamps with cement concrete (1:3:6) using 12mm size hard broken granite chips and curing for 7 days after fixing the clamps including cost, conveyance, royalty, taxes etc. of all materials required for the work and labour charges etc. compl	31.28	Sqm	93.32	Rupees Ninety Three and Thirty Two Paise	2919.05
13	Providing 12mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	167.52	Sqm	200.36	Rupees Two Hundred and Thirty Six Paise	33564.31
14	Providing 16mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	336.13	Sqm	285.74	Rupees Two Hundred Eighty Five and Seventy Four Paise	96045.79
15	6 mm thick cement plaster in cement mortar (1 : 4) including closed deep chipping & slurry treatment including cost, conveyance, royalty & taxes etc. of all materials required for the work,watering, curing, labour charges etc. complete	140.05	Sqm	217.33	Rupees Two Hundred Seventeen and Thirty Three Paise	30437.07
16	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitrified tile (600x600)mm.....etc complete as per direction of the Engineer – in – Charge.	97.80	Sqm	1158.11	Rupees One Thousand One Hundred Fifty Eight and Eleven Paise	113263.16
17	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitrified Industrial Floor tile (300 x 300) mm.....etc complete as per direction of the EIC	29.98	Sqm	986.01	Rupees Nine Hundred Eighty Six and One Paise	29560.58
18	Fixing tiles in dado,skirting & rises of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Vitrified Tile (600x600) mmetc complete as per direction of the Engineer – in – Charge.	21.34	Sqm	1189.30	Rupees One Thousand One Hundred Eighty Nine and Thirty Paise	25379.66
19	Fixing glazed tiles clading on wall over 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Glazed Tile (200x200) mm / (200 x 300) mmetc complete as per direction of the Engineer – in – Charge.	40.95	Sqm	940.96	Rupees Nine Hundred Forty and Ninety Six Paise	38532.31
20	Priming one coat with water bound cement primer of approved quality over plastered surface including scaffolding staging charges with all materials, taxes, labour charges etc compl.	581.40	Sqm	79.31	Rupees Seventy Nine and Thirty One Paise	46110.83
21	Painting 2 coats with water proofing weather coat of approved shade by means of brush to outside surface of walls with cost, carriage of all materials and cost of all labour with T&P required for the work etc. complete as per direction of the Engineer – in – Charge.	167.52	Sqm	95.95	Rupees Ninety Five and Ninety Five Paise	16073.54

	Wall painting two coats with Plastic Emulsion Paint of approved shade on new work to give an even shade including cost, carriage and taxes etc. of all materials required for the work and labour charges etc. complete	413.89	Sqm	102.84	Rupees One Hundred Two and Eighty Four Paise	42564.45
23	Painting two coats with approved enamel paint over a coat of primer of approved quality including cost of enamel paint, primer, brushes & other materials, T. & P. and taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	92.90	Sqm	255.60	Rupees Two Hundred Fifty Five and Sixty Paise	23745.24
24	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete as per direction of EIC	15.85	RM	3864.41	Rupees Three Thousand Eight Hundred Sixty Four and Forty One Paise	61250.90
25	Supplying, fitting and fixing of PVC Door with frame & all fittings including all cost, taxes, labour charges etc complete as per direction of EIC	2.00	Each	3814.00	Rupees Three Thousand Eight Hundred Fourteen Only	7628.00

TOTAL CIVIL COST = Rs 2448427.80

Say 2448427.80
Rupees Twenty Four Lac Forty Eight Thousand Four Hundred Twenty Seven and Eighty Paise

My / Our quoted rate of _____ (both in figures & words)
 Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs.
 Only

Total No. of pages (Enclosed) other than DTCN _____ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.


N.B :- GST, Income Tax, Royalties, Labour cess, EMF, DMF, Additional Charges as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISCON


 J.E. / A.E.
 PARJANG BLOCK


 A.E.E.
 PARJANG BLOCK


 B.D.O
 PARJANG


 Asst. Engineer
 Zilla Parishad, Dhenkanal


 Assistant Executive Engineer
 Zillaparisd.Dhenkanal


 Addl. Executive Officer (Tech.)
 Zilla Parishad, Dhenkanal

BILL OF QUANTITY

NAME OF WORK:-

**Construction of Gram Panchayat Level Federation Office Building with
Market Complex at Pitiri GP of Parjang Block**

AMOUNT PUT TO TENDER :- Rs 2434248.61

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Earth work in excavation of foundation trenches in HARD soil up to the required depth including dressing and leveling the bed and depositing the excavated materials away from the site with all leads and lifts, T&P labour required for the work etc. complete as directed by the Engineer-In Charge.	87.94	Cum	270.90	Rupees Two Hundred Seventy and Ninety Paise	23822.95
2	Cement concrete (1:3:6) in foundation and plinth using 4 cm. size hard granite crusher broken metal of approved quarry and approved quality including hoisting lowering laying concrete in layers not exceeding 0.15 M. in depth including compacting watering and curing etc, complete including cost, conveyance, royalties & of all materials and cost of labour etc with T&P required for the work etc. complete as per specification & direction of Engineer-In-Charge.	21.99	Cum	6708.42	Rupees Six Thousand Seven Hundred Eight and Forty Two Paise	147518.16
3	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Foundation & Plinth including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	12.44	Cum	5887.26	Rupees Five Thousand Eight Hundred Eighty Seven and Twenty Six Paise	73237.51
4	Supplying and filling in foundation and plinth with excavated earth including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	60.20	Cum	150.50	Rupees One Hundred Fifty and Fifty Paise	9060.10
5	Supplying and filling in foundation and plinth with sand including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	32.76	Cum	1436.56	Rupees One Thousand Four Hundred Thirty Six and Fifty Six Paise	47061.71
6	RCC Work M – 20 using 20mm.& down graded black hard crusher broken granite stone chips including hoisting lowering laying and compact concrete by using vibrator watering and curing for 28 days centering shuttering and finishing the exposed surface smooth providing grooves or beads where necessary including cost, conveyance, royalties of all materials and labour with T&P required for the work etc. complete in all respect as per specification & direction of E.I.C					
	A) COLUMN BASE & FOOTINGS	25.19	Cum	7275.59	Rupees Seven Thousand Two Hundred Seventy Five and Fifty Nine Paise	183272.11
	B) PLINTH BEAM	8.20	Cum	8147.51	Rupees Eight Thousand One Hundred Forty Seven and Fifty One Paise	66809.58

	C) COLUMN & BEAM	11.25	Cum	16416.15	Rupees Sixteen Thousand Four Hundred Sixteen and Fifteen Paise	184681.69
	D) LINTEL BAND	3.00	Cum	14886.11	Rupees Fourteen Thousand Eight Hundred Eighty Six and Eleven Paise	44658.33
	E) CHAJJA	10.62	Sqm	1261.87	Rupees One Thousand Two Hundred Sixty One and Eighty Seven Paise	13401.06
	F) ROOF SLAB	15.45	Cum	14451.91	Rupees Fourteen Thousand Four Hundred Fifty One and Ninety One Paise	223282.01
7	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	30.33	Cum	5920.26	Rupees Five Thousand Nine Hundred Twenty and Twenty Six Paise	179561.49
8	Fly ash Brick masonry in cement mortar (1:4) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	4.19	Cum	6167.10	Rupees Six Thousand One Hundred Sixty Seven and Ten Paise	25840.15
9	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars , cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge. (Weight of binding wire shall not be considered for payment in any shape at all).	56.28	Qntl	8522.36	Rupees Eight Thousand Five Hundred Twenty Two and Thirty Six Paise	479638.42
10	Providing & laying 25mm grading concrete (1:2:2) on roof slab using 6mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	125.61	Sqm	410.41	Rupees Four Hundred Ten and Forty One Paise	51551.60
11	Supplying MS door & window shutter with grills (Framed&Fixed) made out of MS angles, flats and sheets etc of approved design & fabrication including cost, conveyance & taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	1342.50	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	113776.88
12	Labour for fitting and fixing of GI doors, windows and gates as per approved design including fixing of door and windows clamps with cement concrete (1:3:6) using 12mm size hard broken granite chips and curing for 7 days after fixing the clams including cost, conveyance, royalty, taxes etc. of all materials required for the work and labour charges etc. compl	31.28	Sqm	93.32	Rupees Ninety Three and Thirty Two Paise	2919.05

	Providing 12mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	167.52	Sqm	200.36	Rupees Two Hundred and Thirty Six Paise	33564.31
14	Providing 16mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	336.13	Sqm	285.74	Rupees Two Hundred Eighty Five and Seventy Four Paise	96045.79
15	6 mm thick cement plaster in cement mortar (1 : 4) including closed deep chipping & slurry treatmant including cost, conveyance, royalty & taxes etc. of all materials required for the work,watering, curing, labour charges etc. complete	140.05	Sqm	217.33	Rupees Two Hundred Seventeen and Thirty Three Paise	30437.07
16	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitrified tile (600x600)mmetc complete as per direction of the Engineer – in – Charge.	97.80	Sqm	1158.11	Rupees One Thousand One Hundred Fifty Eight and Eleven Paise	113263.16
17	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitrified Industrial Floor tile (300 x 300) mmetc complete as per direction of the EIC	29.98	Sqm	986.01	Rupees Nine Hundred Eighty Six and One Paise	29560.58
18	Fixing tiles in dado, skirting & rises of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Vitrified Tile (600x600)mmetc complete as per direction of the Engineer – in – Charge.	21.34	Sqm	1189.30	Rupees One Thousand One Hundred Eighty Nine and Thirty Paise	25379.66
19	Fixing glazed tiles clading on wall over 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Glazed Tile (200x200)mm / (200 x 300) mmetc complete as per direction of the Engineer – in – Charge.	40.95	Sqm	940.96	Rupees Nine Hundred Forty and Ninety Six Paise	38532.31
20	Priming one coat with water bound cement primer of approved quality over plastered surface including scaffolding staging charges with all materials, taxes, labour charges etc compl.	581.40	Sqm	79.31	Rupees Seventy Nine and Thirty One Paise	46110.83
21	Painting 2 coats with water proofing weather coat of approved shade by means of brush to outside surface of walls with cost, carriage of all materials and cost of all labour with T&P required for the work etc. complete as per direction of the Engineer – in – Charge.	167.52	Sqm	95.95	Rupees Ninety Five and Ninety Five Paise	16073.54
22	Wall painting two coats with Plastic Emulsion Paint of approved shade on new work to give an even shade including cost, carriage and taxes etc. of all materials required for the work and labour charges etc. complete	413.89	Sqm	102.84	Rupees One Hundred Two and Eighty Four Paise	42564.45
23	Painting two coats with approved enamel paint over a coat of primer of approved quality including cost of enamel paint, primer,brushes & other materials, T. & P. and taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	92.90	Sqm	255.60	Rupees Two Hundred Fifty Five and Sixty Paise	23745.24

	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete as per direction of EIC	15.85	RM	3864.41	Rupees Three Thousand Eight Hundred Sixty Four and Forty One Paise	61250.90
25	Supplying, fitting and fixing of PVC Door with frame & all fittings including all cost, taxes, labour charges etc complete as per direction of EIC	2.00	Each	3814.00	Rupees Three Thousand Eight Hundred Fourteen Only	7628.00
TOTAL CIVIL COST =						Rs 2434248.61

Say 2434248.61

Rupees Twenty Four Lac Thirty Four Thousand Two Hundred Forty Eight and Sixty One Paise

My / Our quoted rate of _____ (both in figures & words) Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs..... Only

Total No. of pages (Enclosed) other than DTCN _____ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.


N.B :- GST, Income Tax, Royalties, Labour cess, EMF, DMF, Additional Charges as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISCON


05.05.25
J.E./A.E.
PARJANG BLOCK


5/5/25
A.E.E.
PARJANG BLOCK


5/5/25
B.D.O
PARJANG


13/5/25
Asst. Engineer
Zilla Parishad, Dhenkanal


14.5.25
Assistant Executive Engineer
Zillaparisad.Dhenkanal


13/5/25
Asst. Executive Officer (Tech.)
Zilla Parishad, Dhenkanal

BILL OF QUANTITY

NAME OF WORK:-

Construction of Gram Panchayat Level Federation Office Building with
Market Complex at Muktapasi GP of Parjang Block

AMOUNT PUT TO TENDER :- Rs 2456209.⁹⁶00

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Earth work in excavation of foundation trenches in HARD soil up to the required depth including dressing and leveling the bed and depositing the excavated materials away from the site with all leads and lifts, T&P labour required for the work etc. complete as directed by the Engineer-In-Charge.	87.94	Cum	270.90	Rupees Two Hundred Seventy and Ninety Paise	23822.95 ✓
2	Cement concrete (1:3:6) in foundation and plinth using 4 cm. size hard granite crusher broken metal of approved quarry and approved quality including hoisting lowering laying concrete in layers not exceeding 0.15 M. in depth including compacting watering and curing etc. complete including cost ,conveyance, royalties & of all materials and cost of labour etc with T&P required for the work etc. complete as per specification & direction of Engineer-In-Charge.	21.99	Cum	6942.39	Rupees Six Thousand Nine Hundred Forty Two and Thirty Nine Paise	152663.16 ✓
3	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Foundation & Plinth including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	12.44	Cum	5924.08	Rupees Five Thousand Nine Hundred Twenty Four and Eight Paise	73695.56 ✓
4	Supplying and filling in foundation and plinth with excavated earth including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	60.20	Cum	150.50	Rupees One Hundred Fifty and Fifty Paise	9060.10 ✓
5	Supplying and filling in foundation and plinth with sand including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	32.76	Cum	1397.11	Rupees One Thousand Three Hundred Ninety Seven and Eleven Paise	45769.32 ✓

6	RCC Work M – 20 using 20mm.& down graded black hard crusher broken granite stone chips including hoisting lowering laying and compact concrete by using vibrator watering and curing for 28 days centering shuttering and finishing the exposed surface smooth providing grooves or beads where necessary including cost, conveyance, royalties of all materials and labour with T&P required for the work etc. complete in all respect as per specification & direction of E.I.C					
	A) COLUMN BASE & FOOTINGS	25.19	Cum	7494.94	Rupees Seven Thousand Four Hundred Ninety Four and Ninety Four Paise	188797.54
	B) PLINTH BEAM	8.20	Cum	8366.86	Rupees Eight Thousand Three Hundred Sixty Six and Eighty Six Paise	68608.25
	C) COLUMN & BEAM	11.25	Cum	16635.50	Rupees Sixteen Thousand Six Hundred Thirty Five and Fifty Paise	187149.38
	D) LINTEL BAND	3.00	Cum	15105.46	Rupees Fifteen Thousand One Hundred Five and Forty Six Paise	45316.38
	E) CHAJJA	10.62	Sqm	1275.58	Rupees One Thousand Two Hundred Seventy Five and Fifty Eight Paise	13546.66
	F) ROOF SLAB	15.45	Cum	14671.26	Rupees Fourteen Thousand Six Hundred Seventy One and Twenty Six Paise	226670.97
7	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	30.33	Cum	5957.08	Rupees Five Thousand Nine Hundred Fifty Seven and Eight Paise	180678.24

8	Fly ash Brick masonry in cement mortar (1:4) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling chamfering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	4.19	Cum	6203.92	Rupees Six Thousand Two Hundred Three and Ninety Two Paise	25994.42
9	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars , cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge. (Weight of binding wire shall not be considered for payment in any shape at all).	56.28	Qntl	8522.36	Rupees Eight Thousand Five Hundred Twenty Two and Thirty Six Paise	479638.42
10	Providing & laying 25mm grading concrete (1:2:2) on roof slab using 6mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	125.61	Sqm	415.64	Rupees Four Hundred Fifteen and Sixty Four Paise	52208.54
11	Supplying MS door & window shutter with grills (Framed&Fixed) made out of MS angles, flats and sheets etc of approved design & fabrication including cost, conveyance & taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	1342.50	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	113776.88
12	Labour for fitting and fixing of GI doors, windows and gates as per approved design including fixing of door and windows clamps with cement concrete (1:3:6) using 12mm size hard broken granite chips and curing for 7 days after fixing the clams including cost, conveyance, royalty, taxes etc. of all materials required for the work and labour charges etc. compl	31.28	Sqm	93.32	Rupees Ninety Three and Thirty Two Paise	2919.05
13	Providing 12mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	167.52	Sqm	202.33	Rupees Two Hundred Two and Thirty Three Paise	33894.32
14	Providing 16mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge	336.13	Sqm	288.10	Rupees Two Hundred Eighty Eight and Ten Paise	96839.05

15	6 mm thick cement plaster in cement mortar (1 : 4) including closed deep chipping & slurry treatment including cost, conveyance, royalty & taxes etc. of all materials required for the work, watering, curing, labour charges etc. complete	140.05	Sqm	218.32	Rupees Two Hundred Eighteen and Thirty Two Paise	30575.72
16	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitrified tile (600x600)mm..... etc complete as per direction of the Engineer – in – Charge.	97.80	Sqm	1160.87	Rupees One Thousand One Hundred Sixty and Eighty Seven Paise	113533.09
17	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitrified Industrial Floor tile (300 x 300) mm..... etc complete as per direction of the EIC	29.98	Sqm	988.77	Rupees Nine Hundred Eighty Eight and Seventy Seven Paise	29643.32
18	Fixing tiles in dado,skirting & rises of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Vitrified Tile (600x600)mm etc complete as per direction of the Engineer – in – Charge.	21.34	Sqm	1191.27	Rupees One Thousand One Hundred Ninety One and Twenty Seven Paise	25421.70
19	Fixing glazed tiles clading on wall over 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Glazed Tile (200x200)mm / (200 x 300) mm etc complete as per direction of the Engineer – in – Charge.	40.95	Sqm	942.93	Rupees Nine Hundred Forty Two and Ninety Three Paise	38612.98
20	Priming one coat with water bound cement primer of approved quality over plastered surface including scaffolding staging charges with all materials, taxes, labour charges etc compl.	581.40	Sqm	79.31	Rupees Seventy Nine and Thirty One Paise	46110.83
21	Painting 2 coats with water proofing weather coat of approved shade by means of brush to outside surface of walls with cost, carriage of all materials and cost of all labour with T&P required for the work etc. complete as per direction of the Engineer – in – Charge.	167.52	Sqm	95.95	Rupees Ninety Five and Ninety Five Paise	16073.54
22	Wall painting two coats with Plastic Emulsion Paint of approved shade on new work to give an even shade including cost, carriage and taxes etc. of all materials required for the work and labour charges etc. complete	413.89	Sqm	102.84	Rupees One Hundred Two and Eighty Four Paise	42564.45
23	Painting two coats with approved enamel paint over a coat of primer of approved quality including cost of enamel paint, primer, brushes & other materials, T. & P. and taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	92.90	Sqm	255.60	Rupees Two Hundred Fifty Five and Sixty Paise	23745.24

24	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete as per direction of EIC	15.85	RM	3864.41	Rupees Three Thousand Eight Hundred Sixty Four and Forty One Paise	61250.90
25	Supplying, fitting and fixing of PVC Door with frame & all fittings including all cost, taxes, labour charges etc complete as per direction of EIC	2.00	Each	3814.00	Rupees Three Thousand Eight Hundred Fourteen Only	7628.00
TOTAL CIVIL COST					=	Rs 2456208.95

Say **Rs 2456209.00**
Rupees Twenty Four Lac Fifty Six Thousand Two Hundred Nine Only *Eight and Ninty Six Paise) only*

My / Our quoted rate of _____ (both in figures & words)
 Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs.....
 Only

Total No. of pages (Enclosed) other than DTCN _____ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income ^{Tax} Tax, Royalties, ^{EMF, DMF, Additional charges} Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

Mondori
 18/4/25
 J.E.T.A.E.
 PARJANG BLOCK

Saha
 18/4/25
 A.E.E.
 PARJANG BLOCK

Saha
 19/4/25
 B.D.O
 PARJANG

Saha
 23/4/25
 Asst. Engineer
 Zilla Parishad, Dhenkanal

Rangrahi
 24/4/25
 Assistant Executive Engineer
 Zillaparisad.Dhenkanal

Saha
 29/4/25
 Addl. Executive Officer (Tech.)
 Zilla Parishad, Dhenkanal

BILL OF QUANTITY

NAME OF WORK:-

**Construction of Gram Panchayat Level Federation Office Building with
Market Complex at Barihapur GP of Parjang Block**

AMOUNT PUT TO TENDER:-

Rs. 2447838⁷⁸.00

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Earth work in excavation of foundation trenches in HARD soil up to the required depth including dressing and leveling the bed and depositing the excavated materials away from the site with all leads and lifts, T&P labour required for the work etc. complete as directed by the Engineer-In-Charge.	87.94	Cum	270.90	Rupees Two Hundred Seventy and Ninety Paise	23822.95
2	Cement concrete (1:3:6) in foundation and plinth using 4 cm. size hard granite crusher broken metal of approved quarry and approved quality including hoisting lowering laying concrete in layers not exceeding 0.15 M. in depth including compacting watering and curing etc, complete including cost ,conveyance, royalties & of all materials and cost of labour etc with T&P required for the work etc. complete as per specification & direction of Engineer-In-Charge.	21.99	Cum	6866.22	Rupees Six Thousand Eight Hundred Sixty Six and Twenty Two Paise	150988.18
3	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Foundation & Plinth including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	12.44	Cum	5874.43	Rupees Five Thousand Eight Hundred Seventy Four and Forty Three Paise	73077.91
4	Supplying and filling in foundation and plinth with excavated earth including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	60.20	Cum	150.50	Rupees One Hundred Fifty and Fifty Paise	9060.10
5	Supplying and filling in foundation and plinth with sand including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	32.76	Cum	1436.56	Rupees One Thousand Four Hundred Thirty Six and Fifty Six Paise	47061.71

6	RCC Work M – 20 using 20mm.& down graded black hard crusher broken granite stone chips including hoisting lowering laying and compact concrete by using vibrator watering and curing for 28 days centering shuttering and finishing the exposed surface smooth providing grooves or beads where necessary including cost, conveyance, royalties of all materials and labour with T&P required for the work etc. complete in all respect as per specification & direction of E.I.C					
	A) COLUMN BASE & FOOTINGS	25.19	Cum	7423.53	Rupees Seven Thousand Four Hundred Twenty Three and Fifty Three Paise	186998.72 ✓
	B) PLINTH BEAM	8.20	Cum	8295.45	Rupees Eight Thousand Two Hundred Ninety Five and Forty Five Paise	68022.69 ✓
	C) COLUMN & BEAM	11.25	Cum	16564.09	Rupees Sixteen Thousand Five Hundred Sixty Four and Nine Paise	186346.01 ✓
	D) LINTEL BAND	3.00	Cum	15034.05	Rupees Fifteen Thousand Thirty Four and Five Paise	45102.15 ✓
	E) CHAJJA	10.62	Sqm	1271.12	Rupees One Thousand Two Hundred Seventy One and Twelve Paise	13499.29 ✓
	F) ROOF SLAB	15.45	Cum	14599.85	Rupees Fourteen Thousand Five Hundred Ninety Nine and Eighty Five Paise	225567.68 ✓
7	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	30.33	Cum	5907.43	Rupees Five Thousand Nine Hundred Seven and Forty Three Paise	179172.35 ✓

8	Fly ash Brick masonry in cement mortar (1:4) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	4.19	Cum	6154.28	Rupees Six Thousand One Hundred Fifty Four and Twenty Eight Paise	25786.43
9	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars , cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge. (Weight of binding wire shall not be considered for payment in any shape at all).	56.28	Qntl	8522.36	Rupees Eight Thousand Five Hundred Twenty Two and Thirty Six Paise	479638.42
10	Providing & laying 25mm grading concrete (1:2:2) on roof slab using 6mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	125.61	Sqm	413.75	Rupees Four Hundred Thirteen and Seventy Five Paise	51971.14
11	Supplying MS door & window shutter with grills (Framed&Fixed) made out of MS angles, flats and sheets etc of approved design & fabrication including cost, conveyance & taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	1342.50	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	113776.88
12	Labour for fitting and fixing of GI doors, windows and gates as per approved design including fixing of door and windows clamps with cement concrete (1:3:6) using 12mm size hard broken granite chips and curing for 7 days after fixing the clams including cost, conveyance, royalty, taxes etc. of all materials required for the work and labour charges etc. compl	31.28	Sqm	93.32	Rupees Ninety Three and Thirty Two Paise	2919.05
13	Providing 12mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	167.52	Sqm	201.35	Rupees Two Hundred One and Thirty Five Paise	33730.15
14	Providing 16mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	336.13	Sqm	286.92	Rupees Two Hundred Eighty Six and Ninety Two Paise	96442.42

15	6 mm thick cement plaster in cement mortar (1 : 4) including closed deep chipping & slurry treatment including cost, conveyance, royalty & taxes etc. of all materials required for the work,watering, curing, labour charges etc. complete	140.05	Sqm	217.83	Rupees Two Hundred Seventeen and Eighty Three Paise	30507.09
16	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitriified tile (600x600)mm..... etc complete as per direction of the Engineer – in – Charge.	97.80	Sqm	1159.49	Rupees One Thousand One Hundred Fifty Nine and Forty Nine Paise	113398.12
17	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitriified Industrial Floor tile (300 x 300) mm..... etc complete as per direction of the EIC	29.98	Sqm	987.39	Rupees Nine Hundred Eighty Seven and Thirty Nine Paise	29601.95
18	Fixing tiles in dado, skirting & rises of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Vitriified Tile (600x600)mm etc complete as per direction of the Engineer – in – Charge.	21.34	Sqm	1190.28	Rupees One Thousand One Hundred Ninety and Twenty Eight Paise	25400.58
19	Fixing glazed tiles clading on wall over 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Glazed Tile (200x200)mm / (200 x 300) mm etc complete as per direction of the Engineer – in – Charge.	40.95	Sqm	941.95	Rupees Nine Hundred Forty One and Ninety Five Paise	38572.85
20	Priming one coat with water bound cement primer of approved quality over plastered surface including scaffolding staging charges with all materials, taxes, labour charges etc compl.	581.40	Sqm	79.31	Rupees Seventy Nine and Thirty One Paise	46110.83
21	Painting 2 coats with water proofing weather coat of approved shade by means of brush to outside surface of walls with cost, carriage of all materials and cost of all labour with T&P required for the work etc. complete as per direction of the Engineer – in – Charge.	167.52	Sqm	95.95	Rupees Ninety Five and Ninety Five Paise	16073.54
22	Wall painting two coats with Plastic Emulsion Paint of approved shade on new work to give an even shade including cost, carriage and taxes etc. of all materials required for the work and labour charges etc. complete	413.89	Sqm	102.84	Rupees One Hundred Two and Eighty Four Paise	42564.45
23	Painting two coats with approved enamel paint over a coat of primer of approved quality including cost of enamel paint, primer,brushes & other materials, T. & P. and taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	92.90	Sqm	255.60	Rupees Two Hundred Fifty Five and Sixty Paise	23745.24

24	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete as per direction of EIC	15.85	RM	3864.41	Rupees Three Thousand Eight Hundred Sixty Four and Forty One Paise	61250.90
25	Supplying, fitting and fixing of PVC Door with frame & all fittings including all cost, taxes, labour charges etc complete as per direction of EIC	2.00	Each	3814.00	Rupees Three Thousand Eight Hundred Fourteen Only	7628.00
TOTAL CIVIL COST					=	Rs 2447837.78

Say **Rs-2447838.00**
Seven Eight Only and Seventy eight Paise) only

My / Our quoted rate of _____ (both in figures & words)
 Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs.
 Only

Total No. of pages (Enclosed) other than DTCN _____ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income ^{tax}, Royalties, ^{EMF, DMF, Additional charges} Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

Munshi
18/4/25
J.E. / A.E.
PARJANG BLOCK

Shah
18/4/25
A.E.E.
PARJANG BLOCK

19/4/25
B.D.O
PARJANG

Asst. Engineer
23/4/25
Asst. Engineer
Zilla Parishad, Dhenkanal

Rangrahi
24-4-25
Assistant Executive Engineer
Zillaparisad.Dhenkanal

28/4/25
Addl. Executive Officer (Tech.)
Zilla Parishad, Dhenkanal

DETAILED TENDER CALL NOTICE

This detailed Tender Call Notice along with the clauses mentioned herein shall form a part of the contract and agreement. The tenderers are required quote their bidding amount and in percentage both in figures and words placed below the abstract estimate.

The receipt of the bid documents shall start from **Dt. 20.06.25 at 11.00 AM to 05-07-2025 till 5.00 p. m only through Registered Post/ Speed Post addressed to The Block Development Officer Parjang, Dist. Dhenkanal, Odisha, PIN – 759120.**

1. The Bids will be opened on the **Dtd. 08..07.2025 at 11.30 AM** in the office of the undersigned, in the presence of the bidders or their authorized agents who wish to attend, if the office happens to be closed on the date of receipt/opening of the bids as specified, the bids will be received/opened on the next working day at the same time and venue.
2. Tender documents consisting of specification & schedule of quantities (BOQ) and the set of terms and conditions of contract (DTCN) along with other necessary documents can be obtained/downloaded from district NIC website (www.dhenkanal.odisha.gov.in) from **Dt. 20-06-2025 at 10.00 AM to 04-07-2025 till 5.00 p. m**
3. The authority will not be responsible if any portion of the bid document is modified and in all cases this condition stipulated in the original document kept in the Office of the undersigned shall prevail.
4. If, the tender documents sent through registered post/ speed post do not reach the concerned office by the above date and time, the offer will not be considered on any account even if the tender documents were dispatched by the tenderer before the due date.
5. The tenderer has to furnish attested true copy of the original Valid Contractor License / PAN Card / Labor License (not mandatory), GST, Affidavit, Formats along with the tender failing which the tender will be treated as non-responsive and liable for rejection.
6. All tender documents along with paper cost in shape of Demand Draft and the EMD in shape of FDR/TDR/ NSC/ KVP or Small Saving Certificate from any Nationalize Bank duly pledged in favour of Block Development Officer, Parjang in a sealed cover super scribed with name of work shall be sent through post only to the office of the undersigned within the prescribed time. Any tender given by hand to anybody will not be accepted for opening and shall not be considered.
7. The companies or individuals registered with State Government and contractors of equivalent Grade / class registered with Central Government / MES having registration for Civil Works having both legal competency and expertise in Civil Engineering works need put tenders for this work and the documentary evidence under appropriate Act.
8. The contract will be drawn in P.W.D. P1 contract Form.
9. No tender documents will be available to the intending tenderer beyond the date and time of sale mentioned in the tender notice.
10. No tenderers will be permitted to furnish their tender in their own manuscript papers. No letter should accompany the tender.
11. The tender should be strictly in accordance with the provisions as mentioned in the tender schedule. Any change in the wordings will not be accepted.
12. The work is to be completed in all respects as per NIT Col No. 8 from the date of issue of work order. Tenderer whose tender is accepted must submit a programme of work immediately after issue of work order for approval of Engineer-in-Charge.
13. All tenders received will remain valid for a period of 90 days from the last date prescribed for receipt of tenders and validity of tenders can also be extended if agreed by the tenderers and the Department.