

**GOVERNMENT OF ODISHA**  
**INVITATION FOR BIDS (IFB)**  
 Identification No.03/ BDO Parjang  
**TENDER CALL NOTICE NO. 03 OF 2025-26**


***E-mail : [ori-Parjang@nic.in](mailto:ori-Parjang@nic.in)***

1. Block Development Officer, Parjang on behalf of Governor of Odisha invites percentage rate bids for the works (civil only) as detailed in the table from class of contractors mentioned in Col.-4 below registered with the State Government and contractors of equivalent grade / class registered with Central Government / MES / Railways to be eventually drawn up in PWD F-2 (Now P-1) form for execution of civil works, on production of definite proof from the appropriate authority. But successful bidder of other State / MES / Railway / CPWD in equivalent rank has to register under the State PWD before signing the agreement. The bidders may submit bid for the work.

Sl. No.	Name of the work.	Approximate value of work	Class of contractor	Place of receipt of tender papers through Post only.	Cost of BID documents (Non-refundable (Rs.))	EMD 1 %	Period of completion in months
1	2	3	4	5	6	7	8
1	Construction of Proposed Office Building at Kumusi GP under Parjang Block in the District of Dhenkanal	Rs.10,52,279.08	C & D Class	BDO, Parjang	Rs.6,000	Rs 10523.00	6 (Six Calendar Month)
2	Construction of Proposed 50MT Godowan at Kumusi GP under parjang Block in the District of Dhenkanal	Rs.13,64,756.78	C & D Class	BDO, Parjang	Rs.6,000	Rs 13648.00	6 (Six Calendar Month)


2. Tender documents consisting of specification & schedule of quantities (BOQ) and the set of terms and conditions of contract (DTCN) along with other necessary documents can be obtained/downloaded from district NIC website ([www.dhenkanal.odisha.gov.in](http://www.dhenkanal.odisha.gov.in)) from **Dt. 20.06.2025 10.00 AM to 04.07.2025 till 5.00 p.m.** Interested bidders may obtain further information at the address mentioned in Col.5 above.
3. Sealed Bids must be enclosed with appropriate paper cost in shape of a **non-refundable Demand Draft, separately issued in favour of Block Development Officer Parjang & payable at Parjang**
4. **The Earnest Money Deposit (EMD) will be 1 % of the Tender value and should be deposited in shape TDR, FDR, NSC, KVP or small saving deposit from any Nationalized Bank duly pledged in favour of "Block Development Officer", Parjang payable at Parjang at the time of Bidding.**
5. The receipt of the bid documents will start from **Dt. 20.06.2025 at 10.00 AM to 05.07.2025 till 5.00 p. m only through Registered Post/ Speed Post** addressed to **The Block Development Officer Parjang, Dist. - Dhenkanal, Odisha, PIN – 759120.** Delay due to postal will not be considered at any cost.
6. The bids will be opened on **Dt-08-07-2025 at 11.30 AM** in the office of the under signed in the presence of the bidders or their authorized persons who wish to attend. If the office

- happens to be closed on the opening day, the bids will be opened on the next working day at the same time and venue accordingly.
7. Bidding documents will be available in the District website i.e. Dhenkanal.nic.in and the same can be downloaded and submitted along with the relevant documents duly filled up and the same can be submitted to **The Block Development Officer Parjang by Registered Post/ Speed post within the stipulated time mentioned above and the Authority will not be held responsible for any kind of postal delay (dispatching Bid documents/receiving sealed Bids), if any.**
  8. Sealed Bids should be accompanied with the attested true copies of the valid registration certificate, GSTIN, PAN card, Affidavit and other documents as per DTCN which are mandatory and the original documents submitted by the successful bidder will be verified within five working days of opening of the tender before Block Development Officer Parjang for verification otherwise his / her bids shall be declared as non-responsive and thus liable for rejection and the bidder will be as Black Listed for 2 years from the Department and the EMD amount will be forfeited. The same tender will be rendered further.
  9. Other details can be seen in the bidding documents.
  10. The enclosures other than the D.T.C.N. should be page numbered and signed by the contractor.
  11. Total No. of enclosures should be submitted by him / her in Numbers and words as per relevant clause of D.T.C.N.
  12. The authority reserves the right to reject any or all tenders without assigning any reason thereof.
  13. The Bid Documents can be downloaded from the Dhenkanal Portal i.e. [www,Dhenkanal.nic.in](http://www.Dhenkanal.nic.in).

  
Block Development Officer  
Parjang


Memo No. 3093 Dt. 16/6/25

Copy submitted to the Collector & District Magistrate, Dhenkanal / CDO-Cum-EO, ZP, Dhenkanal / Sub-Collector, Kamakshyanagar with a request to display the above notice in the office Notice Board for wide circulation.

  
Block Development Officer  
Parjang

Memo No. 3094 Dt. 16/6/25

Copy to the D.I.O, Dhenkanal for information & necessary action. One copy of this notice & other tender documents (DTCN & BOQ) may be hoisted in the district website for wide circulation.

  
Block Development Officer  
Parjang

Memo No. 3095 Dt. 16/6/25

Copy to the Director, Information & Public Relation Department, Bhubaneswar for publishing of Tender Notice in two Odia & One English daily News Paper for wide circulation.

13/6/25  
Block Development Officer  
Parjang

Memo No. 3096 Dt. 16/6/25

Copy to Accounts Section/ RSO/ Cashier/ Office Notice Board of this office for kind information.

13/6/25  
Block Development Officer  
Parjang

## BILL OF QUANTITY

NAME OF WORK:-	CONSTRUCTION OF PROPOSED OFFICE BUILDING KUMUSI GP UNDER PARJANG BLOCK IN THE DISTRICT OF DHENKANAL.
----------------	--

AMOUNT PUT TO TENDER:-      Rs      1052279.00

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Earth work in excavation in all kinds of soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge	21.80	Cum	270.90	Rupees Two Hundred Seventy and Ninety Paise	5905.62
2	Sand filling in foundation and plinth including cost of all material, labour, conveyance, loading and unloading, taxes, royalties, sundries, tools and plants etc. complete as per the direction of the Engineer in Charge. (linear measurement will be taken and quantity will be calculated on standard weight for all heights).	37.70	Cum	1436.56	Rupees One Thousand Four Hundred Thirty Six and Fifty Six Paise	54158.31
3	Filling foundation & plinth with excavated earth well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	14.53	Cum	150.50	Rupees One Hundred Fifty and Fifty Paise	2186.77
4	Providing & laying plain cement concrete (1:3:6) using 4cm size metal etc. complete including all labour, materials & royalty etc. complete as per direction of EIC.	9.00	Cum	7000.03	Rupees Seven Thousand and Three Paise	63000.27
5	<b>RCC Work M – 20</b> using 20mm. & down graded black hard crusher broken granite stone chips including hoisting lowering laying and compact concrete by using vibrator watering and curing for 28 days centering shuttering and finishing the exposed surface smooth providing grooves or beads where necessary including cost, conveyance, royalties of all materials and labour with T&P required for the work etc. complete in all respect as per specification & direction of E.I.C					
	a) Base Footing	3.500	Cum	7548.98	Rupees Seven Thousand Five Hundred Forty Eight and Ninety Eight Paise	26421.43
	(b) Column in s/s	3.40	Cum	16689.54	Rupees Sixteen Thousand Six Hundred Eighty Nine and Fifty Four Paise	56744.44
	(c) Plinth beam	3.050	Cum	8420.90	Rupees Eight Thousand Four Hundred Twenty and Ninety Paise	25683.75

	(d) Lintel band	1.480	Cum	15159.50	Rupees Fifteen Thousand One Hundred Fifty Nine and Fifty Paise	22436.06 ✓
	(e) Chajja(.0625 mm thick)	6.690	Cum	1278.96	Rupees One Thousand Two Hundred Seventy Eight and Ninety Six Paise	8556.24 ✓
	(g) Roof Beam	3.750	Cum	16689.54	Rupees Sixteen Thousand Six Hundred Eighty Nine and Fifty Four Paise	62585.78 ✓
	(h) Roof slab	5.530	Cum	14725.30	Rupees Fourteen Thousand Seven Hundred Twenty Five and Thirty Paise	81430.91 ✓
6	Supplying,Cutting,straightening of steel HYSD (Fe- 500) conforming to (IS- 1786) with bending, binding, cranking, hooking, welding or jointing if necessary & tying the grills and placing in position as required for the Rod work in all floors and & for providing fan hooks hosting lowering ,& laying steels including cost conveyance ,taxes & royalties of all materials and binding wires of 18 to 20 gauge & cost of all labour T&P required for the work etc. Complete in all respect as per the direction of Engineer in rod or tor steel only basing on the co- efficient of MS rod or tor steel bars approved by SAIL/ TATA/ competent authority and (No separate payment will be made towards the cost of binding wires over lapping, wastage, coupling, welded, joints , spacer bars, ,chairs stays, hangers and annealed steel wires or other methods for binding and placing etc.)	23.920	Qtl	8569.38	Rupees Eight Thousand Five Hundred Sixty Nine and Thirty Eight Paise	204979.57 ✓
7	Fly ash brick masonry of size 25cmx12cmx8cm and crushing strength not less than 75 kg/cm2 in C.M.(1:6) in F&P including cost of all material, labour, conveyance, royalty, loading and unloading, sundries, tools and plants etc. complete as per the direction of the Engineer in Charge.	7.240	Cum	5874.43	Rupees Five Thousand Eight Hundred Seventy Four and Forty Three Paise	42530.87 ✓
8	Fly ash brick masonry of size 25cmx12cmx8cm and crushing strength not less than 75 kg/cm2 in C.M.(1:6) in Super structure including cost of all material, labour, conveyance, royalty, loading and unloading, sundries, tools and plants etc. complete as per the direction of the Engineer in Charge.	20.350	cum	5907.43	Rupees Five Thousand Nine Hundred Seven and Forty Three Paise	120216.20 ✓
9	Supplying of G I door & windows shutter with grills and ventilator (Framed & fixed) made out of MS angles , flats, sheets of approved design and fabrication including cost of conveyance, taxes of all materials required for the work and labour charges etc complete .as per the direction of the Engineer in Charge.	853.400	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	72325.65 ✓

10	Labour charges for fitting and fixing of GI door , windows ,ventilator as per approved design oncluding fixing of door and windows clamps with cement concrete (1:3:6) using 12 mm size hard broken granite chips and curing for 7 days after fixing the clamps including cost, conveyance ,taxes etc all materials required for the work and labour charges etc complete.	15.440	Sqm	93.32	Rupees Ninety Three and Thirty Two Paise	1440.86
11	Providing 6 mm thick cement plaster in cm (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment including cost of all materials, labour, conveyance, loading and unloading, taxes, royalties, sundries, tols and plants etc. complete as per the driection of the Engineer in Charge.	69.270	Sqm	217.83	Rupees Two Hundred Seventeen and Eighty Three Paise	15089.08
12	Providing 12mm thick cement plaster in cm (1:6) on the rough surface/ plumbed surface of masonry racking out of joints, scrapping and cleaning the surface and finishing the plastered surface smooth to proper plumbs and level and providing grooves as shown in the drawing including cost of all material, labour, conveyance, loading and unloading, taxes,	85.940	Sqm	201.35	Rupees Two Hundred One and Thirty Five Paise	17304.02
13	Providing 16mm thick cement plaster in cm (1:6) on the rough surface of masonry walls for all floors including racking and joints, scrapping and cleaning the surface and finishing the plastered surface smooth to proper plumbs and level and providing grooves as shown in the drawing including cost of all material, labour, conveyance, loading and unloading, taxes, royalties, sundries, tools and plants etc. complete as per the driection of the Engineer in Charge.	118.750	Sqm	286.92	Rupees Two Hundred Eighty Six and Ninety Two Paise	34071.75
14	Supplying & fixing of vitrified tiles on 20 mm thick bed of cement mortar (1:4) jointed with neat cement slury mixed with pigment to match the shades of the tiles including all taxes etc complete.	50.130	Sqm	1162.79	Rupees One Thousand One Hundred Sixty Two and Seventy Nine Paise	58290.66
15	Supplying & fixing of vitrified tiles on 12 mm thick bed of cement mortar (1:3) jointed with neat cement slury mixed with pigment to match the shades of the tiles including all taxes etc complete.	23.630	Sqm	1193.59	Rupees One Thousand One Hundred Ninety Three and Fifty Nine Paise	28204.53
16	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete.	179.38	Sqm	91.42	Rupees Ninety One and Forty Two Paise	16398.92
17	Distempering two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper per 1 sqm.....etc compl.	179.38	Sqm	86.61	Rupees Eighty Six and Sixty One Paise	15536.10
18	Finishing wall surface with two coats of weather coat over a coat of cement priming including cost and conveyance of all materials, labour T&P, hire charges of machine, all taxes etc all	94.58	Sqm	95.95	Rupees Ninety Five and Ninety Five Paise	9074.95

19	Painting two coats of synthetic enamel paint over including cost and conveyance of all materials, labour T&P, hire charges of machine, all taxes etc all completes in all respects as per the direction of Engineer charges.	30.15	sqm	255.60	Rupees Two Hundred Fifty Five and Sixty Paise	7706.34
----	--	-------	-----	--------	---	---------

**TOTAL** 1052279.07  
**Say,** **1052279.00**

**Rupees Ten Lac Fifty Two Thousand Two Hundred Seventy Nine Only**  
*and eight paise) only*

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words )  
 Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs.....  
 .....Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

*[Signature]*  
 18/4/25  
 J.E. / A.E.  
 PARJANG BLOCK

*[Signature]*  
 18/4/25  
 A.E.E.  
 PARJANG BLOCK

*[Signature]*  
 19/4/25  
 B.D.O  
 PARJANG

*[Signature]*  
 23/4/25  
 Asst. Engineer  
 Zillaparisad.Dhenkanal

*[Signature]*  
 24.4.25  
 Assistant Executive Engineer  
 Zillaparisad.Dhenkanal

*[Signature]*  
 29/4/25  
 Addl. Executive Officer (Tech.)  
 Zilla Parishad, Dhenkanal

## BILL OF QUANTITY

NAME OF WORK:-	CONSTRUCTION OF PROPOSED 50 MT GODOWN AT KUMUSI GP UNDER PARJANG BLOCK IN THE DISTRICT OF DHENKANAL.
----------------	--

AMOUNT PUT TO TENDER :- Rs Rs. 1364757.<sup>78</sup>~~00~~

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Earth work in excavation in all kinds of soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge	23.45	Cum	270.90	Rupees Two Hundred Seventy and Ninety Paise	6352.61
2	Sand filling in foundation and plinth including cost of all material, labour, conveyance, loading and unloading, taxes, royalties, sundries, tools and plants etc. complete as per the direction of the Engineer in Charge. (linear measurement will be taken and quantity will be calculated on standard weight for all heights).	44.75	Cum	1436.56	Rupees One Thousand Four Hundred Thirty Six and Fifty Six Paise	64286.06
3	Providing & laying plain cement concrete (1:3:6) using 4cm size metal etc. complete including all labour, materials & royalty etc. complete as per direction of EIC.	9.360	Cum	7000.03	Rupees Seven Thousand and Three Paise	65520.28
4	Filling foundation & plinth with excavated earth well watered & rammed including cost, conveyance, royalty & taxes etc. of all materials required for the work, labour charges etc. complete as per the specification & direction of EIC	29.830	Cum	150.50	Rupees One Hundred Fifty and Fifty Paise	4489.42
5	<b>RCC Work M – 20</b> using 20mm.& down graded black hard crusher broken granite stone chips including hoisting lowering laying and compact concrete by using vibrator watering and curing for 28 days centering shuttering and finishing the exposed surface smooth providing grooves or beads where necessary including cost, conveyance, royalties of all materials and labour with T&P required for the work etc. complete in all respect as per specification & direction of E.I.C					
	a) Base Footing	4.090	Cum	7548.98	Rupees Seven Thousand Five Hundred Forty Eight and Ninety Eight Paise	30875.33
	(b) Column in s/s					
	Up to 3.0 mtr Height	3.600	Cum	16689.54	Rupees Sixteen Thousand Six Hundred Eighty Nine and Fifty Four Paise	60082.34

	Above 3.0 mtr Height	1.510	Cum	18695.39	Rupees Eighteen Thousand Six Hundred Ninety Five and Thirty <del>Nine</del> Eight Paise	28230.03
	(c) Plinth beam	3.310	Cum	8420.90	Rupees Eight Thousand Four Hundred Twenty and Ninety Paise	27873.18
	(d) Lintel band	0.520	Cum	15159.50	Rupees Fifteen Thousand One Hundred Fifty Nine and Fifty Paise	7882.94
	(e) Chajja	2.210	Cum	1278.96	Rupees One Thousand Two Hundred Seventy Eight and Ninety <del>Five</del> Paise	2826.40
	(g) Roof Beam	1.400	Cum	18695.39	Rupees Eighteen Thousand Six Hundred Ninety Five and Thirty <del>Nine</del> Eight Paise	26173.54
6	Supplying, Cutting, straightening of steel HYSD (Fe 500) conforming to (IS- 1786) with bending, binding, cranking, hooking, welding or jointing if necessary & tying the grills and placing in position as required for the Rod work in all floors and & for providing fan hooks hosting lowering ,& laying steels including cost conveyance ,taxes & royalties of all materials and binding wires of 18 to 20 gauge & cost of all labour T&P required for the work etc. Complete in all respect as per the direction of Engineer in charges ( payment will be made on weight of MS rod or tor steel only basing on the co- efficient of MS rod or tor steel bars approved by SAIL/ TATA/ competent authority and (No separate payment will be made towards the cost of binding wires over lapping, wastage, coupling, welded, joints , spacer bars, ,chairs stays, hangers and annealed steel wires or other methods for binding and placing etc.)	17.340	Qtl	8569.38	Rupees Eight Thousand Five Hundred Sixty Nine and Thirty Eight Paise	148593.05
7	Fly ash brick masonry of size 25cmx12cmx8cm and crushing strength not less than 75 kg/cm2 in C.M.(1:6) in F&P including cost of all material, labour, conveyance, royalty, loading and unloading, sundries, tools and plants etc. complete as per the direction of the Engineer in Charge.	12.880	Cum	5874.43	Rupees Five Thousand Eight Hundred Seventy Four and Forty Three Paise	75662.66
8	Fly ash brick masonry of size 25cmx12cmx8cm and crushing strength not less than 75 kg/cm2 in C.M.(1:6) in Super structure including cost of all material, labour, conveyance, royalty, loading and unloading, sundries, tools and plants etc. complete as per the direction of the Engineer in Charge.					

	Up to 3.0 mtr Height	23.800	cum	5907.43	Rupees Five Thousand Nine Hundred Seven and Forty Three Paise	140596.83
	Above 3.0 mtr Height	15.950	Rs.	6226.66	Rupees Six Thousand Two Hundred Twenty Six and Sixty Six Paise	99315.23
9	Supplying of GI door & widows shutter with grill (framed & fixed ) made of MS angles, flats and sheets etc of approved design and fabrication including cost of all materials, l conveyance, taxes etc of all materials required for the work labour chrges etc complete as per the direction of the Engineer in Charge.					
	Door& shuter	452.000	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	38307.00
	Grills	183.600	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	15560.10
10	Labour charges for fitting and fixing GI door & widows and grills as per approved design including fixing of door and windows clamps with cement concrete (1:3:6) using 12 mm granite chips and curing 7 days after fixing the clamps including cost of conveyance, taxes etc of all materials required for the work etc complete.	17.420	Kg	93.32	Rupees Ninety Three and Thirty Two Paise	1625.63
11	Providing 12mm thick cement plaster in cm (1:6) on the rough surface/ plumbed surface of masonry racking out of joints, scrapping and cleaning the surface and finishing the plastered surface smooth to proper plumbs and level and providing grooves as shown in the drawing including cost of all material, labour, conveyance, loading and unloading, taxes, royalties, sundries, tools and plants etc. complete as per the drection of the Engineer in Charge.					
	Up to 3.0 mtr Height	100.310	Sqm	201.35	Rupees Two Hundred One and Thirty Five Paise	20197.42
	Above 3.0 mtr Height	79.180	Sqm	205.30	Rupees Two Hundred Five and Thirty Paise	16255.65
12	Providing 16mm thick cement plaster in cm (1:6) on the rough surface of masonry walls for all floors including racking and joints, scrapping and cleaning the surface and finishing the plastered surface smooth to proper plumbs and level and providing grooves as shown in the drawing including cost of all material, labour, conveyance, loading and unloading, taxes, royalties, sundries, tools and plants etc. complete as per the drection of the Engineer in Charge.					

	Up to 3.0 mtr Height	125.090	Sqm	286.92	Rupees Two Hundred Eighty Six and Ninety Two Paise	35890.82
	Above 3.0 mtr Height	60.560	Sqm	292.82	Rupees Two Hundred Ninety Two and Eighty Two Paise	17733.18
13	25mm thick AS Flooring using 12 mm cbg chips including punning including cost, conveyance, royalty & taxes etc. of all materials required for the work, watering, curing, labour charges etc. complete	22.02	Sqm	430.51	Rupees Four Hundred Thirty and Fifty One Paise	9479.83
14	Providing & laying Cement Concrete ( 1:2:4 ) using 12mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing for 21 days, labour charges etc. complete as per the specification & direction of EIC	2.81	cum	8620.47	Rupees Eight Thousand Six Hundred Twenty and Forty Seven Paise	24223.52
15	Distempering two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper per 1 sqm.....etc compl.					
	Up to 3.0 mtr Height	125.09	Sqm	86.61	Rupees Eighty Six and Sixty One Paise	10834.04
	Above 3.0 mtr Height	60.56	Rs.	88.39	Rupees Eighty Eight and Thirty Eight Paise	5352.89
16	Finishing wall surface with two coats of weather coat over a coat of cement priming including cost and conveyance of all materials, labour T&P, hire charges of machine, all taxes etc all completes in all respects as per the direction of Engineer charges.					
	Up to 3.0 mtr Height	100.31	sqm	95.95	Rupees Ninety Five and Ninety Five Paise	9624.74
	Above 3.0 mtr Height	79.18	Rs.	99.02	Rupees Ninety Nine and Two Paise	7840.40
17	Supplying, fabrication ,fitting, fixing & erection of mms tubular truss & purlin including all cost , conveyance etc complete.	18.64	Qntl	13634.00	Rupees Thirteen Thousand Six Hundred Thirty Four Only	254137.76
18	Labour charges and fabrication work including weldind the purlin channel with angle truses and nu tbolt channel purlin,runner and Fender to plinth band angular including fabrication and fixing in position including all cost , conveyance etc complete.	15.00	MD	452.00	Rupees Four Hundred Fifty Two Only	6780.00
19	Painting two coats of synthetic enamel paint over including cost and conveyance of all materials, labour T&P, hire charges of machine, all taxes etc all completes in all respects as per the direction of Engineer charges.	25.83	sqm	255.60	Rupees Two Hundred Fifty Five and Sixty Paise	6602.15

20	Cost , Supplying and labour for fixing of anti corrosive zinc aluminium alloy painted coloured steel roofing profile sheet of 0.45 mm thick in roof of godown including fixing with fasteners etc complete as directed by EIC.	92.61	Sqm	1007.40	Rupees One Thousand Seven and Forty Paise	93295.31
21	Labour charges for fixing glass strips of depth 0.05m in joints in floor including cost of glass per 1 meter.	3.24	Sqm	696.40	Rupees Six Hundred Ninety Six and Forty Paise	2256.34

TOTAL 1364756.78  
Say, 1364757.00

**Rupees Thirteen Lac Sixty Four Thousand Seven Hundred Fifty Seven Only**  
*and Seventy eight paise only* <sup>Six</sup>

My / Our quoted rate of \_\_\_\_\_ ( both in figures & words )  
Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs.....  
..... Only

Total No. of pages ( Enclosed ) other than DTCN \_\_\_\_\_ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

*[Signature]*  
18.4.25  
J.E. / A.E.  
PARJANG BLOCK

*[Signature]*  
18/4/25  
A.E.E.  
PARJANG BLOCK

*[Signature]*  
19/4/25  
B.D.O  
PARJANG

*[Signature]*  
23/4/25  
Asst. Engineer  
Zilla Parishad, Dhenkanal

*[Signature]*  
24.4.25  
Assistant Executive Engineer  
Zillaparisad.Dhenkanal

*[Signature]*  
29/4/25  
Addl. Executive Officer (Tech.)  
Zilla Parishad, Dhenkanal