

GOVERNMENT OF ODISHA

INVITATION FOR BIDS (IFB)

Identification No.02/ BDO Parjang

TENDER CALL NOTICE NO. 02 OF 2025-26


E-mail :ori-Parjang@nic.in

1. Block Development Officer, Parjang on behalf of Governor of Odisha invites percentage rate bids for the works (civil only) as detailed in the table from class of contractors mentioned in Col.-4 below registered with the State Government and contractors of equivalent grade / class registered with Central Government / MES / Railways to be eventually drawn up in PWD F-2 (Now P-1) form for execution of civil works, on production of definite proof from the appropriate authority. But successful bidder of other State / MES / Railway / CPWD in equivalent rank has to register under the State PWD before signing the agreement. The bidders may submit bid for the work.

Sl. No.	Name of the work.	Approximate value of work	Class of contractor	Place of receipt of tender papers through Post only.	Cost of BID documents (Non-refundable (Rs.))	EMD 1 %	Period of completion in months
1	2	3	4	5	6	7	8
1	Construction of Additional Class Room of Naranapada Pry. School, Kalada	Rs.13,51,149.91	C & D Class	BDO, Parjang	Rs.6,000	Rs 13511.00	6 (Six Calendar Month)
2	Construction of additional class room of Visvesvara Vidya Pitha, Mundeilo	Rs.14,61,149.89	C & D Class	BDO, Parjang	Rs.6,000	Rs 14611.00	6 (Six Calendar Month)

2. Tender documents consisting of specification & schedule of quantities (BOQ) and the set of terms and conditions of contract (DTCN) along with other necessary documents can be obtained/downloaded from district NIC website (www.dhenkanal.odisha.gov.in) from Dt. 20.06.2025 10.00 AM to 04.07.2025 till 5.00 p.m. Interested bidders may obtain further information at the address mentioned in Col.5 above.
3. Sealed Bids must be enclosed with appropriate paper cost in shape of a **non-refundable Demand Draft, separately issued in favour of Block Development Officer Parjang & payable at Parjang**
4. **The Earnest Money Deposit (EMD) will be 1 % of the Tender value and should be deposited in shape TDR, FDR, NSC, KVP or small saving deposit from any Nationalized Bank duly pledged in favour of "Block Development Officer", Parjang payable at Parjang at the time of Bidding.**
5. The receipt of the bid documents will start from Dt. 20.06.2025 at 10.00 AM to 05.07.2025 till 5.00 p. m only through Registered Post/ Speed Post addressed to The Block Development Officer Parjang, Dist. - Dhenkanal, Odisha, PIN - 759120. Delay due to postal will not be considered at any cost.
6. The bids will be opened on Dt-08-07-2025 at 11.30 AM in the office of the under signed in the presence of the bidders or their authorized persons who wish to attend. If the office happens to be closed on the opening day, the bids will be opened on the next working day at the same time and venue accordingly.

7. Bidding documents will be available in the District website i.e. Dhenkanal.nic.in and the same can be downloaded and submitted along with the relevant documents duly filled up and the same can be submitted to **The Block Development Officer Parjang by Registered Post/ Speed post within the stipulated time mentioned above and the Authority will not be held responsible for any kind of postal delay (dispatching Bid documents/receiving sealed Bids), if any.**
8. Sealed Bids should be accompanied with the attested true copies of the valid registration certificate, GSTIN, PAN card, Affidavit and other documents as per DTCN which are mandatory and the original documents submitted by the successful bidder will be verified within five working days of opening of the tender before Block Development Officer Parjang for verification otherwise his / her bids shall be declared as non-responsive and thus liable for rejection and the bidder will be as Black Listed for 2 years from the Department and the EMD amount will be forfeited. The same tender will be rendered further.
9. Other details can be seen in the bidding documents.
10. The enclosures other than the D.T.C.N. should be page numbered and signed by the contractor.
11. Total No. of enclosures should be submitted by him / her in Numbers and words as per relevant clause of D.T.C.N.
12. The authority reserves the right to reject any or all tenders without assigning any reason thereof.
13. The Bid Documents can be downloaded from the Dhenkanal Portal i.e. [www,Dhenkanal.nic.in](http://www.Dhenkanal.nic.in).


Block Development Officer
Parjang

Memo No. 3088 Dt. 16/6/25

Copy submitted to the Collector & District Magistrate, Dhenkanal / CDO-Cum-EO, ZP, Dhenkanal / Sub-Collector, Kamakshyanagar with a request to display the above notice in the office Notice Board for wide circulation.


Block Development Officer
Parjang

Memo No. 3089 Dt. 16/6/25

Copy to the D.I.O, Dhenkanal for information & necessary action. One copy of this notice & other tender documents (DTCN & BOQ) may be hoisted in the district website for wide circulation.


Block Development Officer
Parjang

Memo No. 3090 Dt. 16/6/25

Bhubaneswar

Copy to the Director, Information & Public Relation Department, for publishing of Tender Notice in two Odia & One English daily News Paper for wide circulation.

13/6/25
Block Development Officer
Parjang

Memo No. 3091 Dt. 16/6/25

Copy to Accounts Section/ RSO/ Cashier/ Office Notice Board of this office for kind information.

13/6/25
Block Development Officer
Parjang

BILL OF QUANTITY

NAME OF WORK:-

Construction of Additional Class Room of Naranapada Pry. School, Kalada

AMOUNT PUT TO TENDER :-

Rs 1351149.⁹¹~~00~~

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Earth work in excavation of foundation trenches in HARD soil up to the required depth including dressing and leveling the bed and depositing the excavated materials away from the site with all leads and lifts, T&P labour required for the work etc. complete as directed by the Engineer-In Charge.	67.30	Cum	270.90	Rupees Two Hundred Seventy and Ninety Paise	18231.57
2	Cement concrete (1:3:6) in foundation and plinth using 4 cm. size hard granite crusher broken metal of approved quarry and approved quality including hoisting lowering laying concrete in layers not exceeding 0.15 M. in depth including compacting watering and curing etc, complete including cost ,conveyance, royalties & of all materials and cost of labour etc with T&P required for the work etc. complete as per specification & direction of Engineer-In-Charge.	14.77	Cum	6866.22	Rupees Six Thousand Eight Hundred Sixty Six and Twenty Two Paise	101414.07
3	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Foundation & Plinth including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	8.82	Cum	5874.43	Rupees Five Thousand Eight Hundred Seventy Four and Forty Three Paise	51812.47
4	Supplying and filling in foundation and plinth with excavated earth including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	37.25	Cum	150.50	Rupees One Hundred Fifty and Fifty Paise	5606.13
5	Supplying and filling in foundation and plinth with sand including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	26.24	Cum	1436.56	Rupees One Thousand Four Hundred Thirty Six and Fifty Six Paise	37695.33
6	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc.	16.92	Cum	5907.43	Rupees Five Thousand Nine Hundred Seven and Forty Three Paise	99953.72

7	RCC Work M - 20 using 20mm.& down graded black hard crusher broken granite stone chips including hoisting lowering laying and compact concrete by using vibrator watering and curing for 28 days centering shuttering and finishing the exposed surface smooth providing grooves or beads where necessary including cost, conveyance, royalties of all materials and labour with T&P required for the work etc. complete in all respect as per specification & direction of E.I.C					
	A) COLUMN BASE & FOOTINGS	12.57	Cum	7423.53	Rupees Seven Thousand Four Hundred Twenty Three and Fifty Three Paise	93313.77 ✓
	B) PLINTH BEAM	2.63	Cum	8295.45	Rupees Eight Thousand Two Hundred Ninety Five and Forty Five Paise	21817.03 ✓
	C) COLUMN & BEAM	8.02	Cum	16564.09	Rupees Sixteen Thousand Five Hundred Sixty Four and Nine Paise	132844.00 ✓
	D) LINTEL BAND	1.74	Cum	15034.05	Rupees Fifteen Thousand Thirty Four and Five Paise	26159.25 ✓
	E) CHAJJA	11.64	Sqm	1271.12	Rupees One Thousand Two Hundred Seventy One and Twelve Paise	14795.84 ✓
	F) ROOF SLAB	9.50	Cum	14599.85	Rupees Fourteen Thousand Five Hundred Ninety Nine and Eighty Five Paise	138698.58 ✓
8	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars , cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge.(Weight of binding wire shall not be considered for payment in any shape at all).	32.38	Qntl	8533.67	Rupees Eight Thousand Five Hundred Thirty Three and Sixty Seven Paise	276320.23 ✓
9	Providing 12mm thick cement plaster (1:4) finished smooth over roof slab including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	74.22	Sqm	215.27	Rupees Two Hundred Fifteen and Twenty Seven Paise	15977.34 ✓
10	Supplying MS door & window shutter with grills (Framed&Fixed) made out of MS angles, flats and sheets etc of approved design & fabrication including cost, conveyance & taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	520.00	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	44070.00 ✓

11	Labour for fitting and fixing of GI doors, windows and gates as per approved design including fixing of door and windows clamps with cement concrete (1:3:6) using 12mm size hard broken granite chips and curing for 7 days after fixing the clams including cost, conveyance, royalty, taxes etc. of all materials required for the work and labour charges etc. compl	11.89	Sqm	93.32	Rupees Ninety Three and Thirty Two Paise	1109.57
12	Providing 12mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complete as per direction of Engineer-In-Charge.	112.80	Sqm	201.35	Rupees Two Hundred One and Thirty Five Paise	22712.28
13	Providing 16mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complete as per direction of Engineer-In-Charge.	133.37	Sqm	286.92	Rupees Two Hundred Eighty Six and Ninety Two Paise	38266.52
14	6 mm thick cement plaster in cement mortar (1 : 4) including closed deep chipping & slurry treatment including cost, conveyance, royalty & taxes etc. of all materials required for the work,watering, curing, labour charges etc. complete	90.52	Sqm	217.83	Rupees Two Hundred Seventeen and Eighty Three Paise	19717.97
15	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitified tile (600x600)mm..... etc complete as per direction of the Engineer – in – Charge.	62.07	Sqm	1159.49	Rupees One Thousand One Hundred Fifty Nine and Forty Nine Paise	71969.54
16	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitified Industrial Floor tile etc complete as per direction of the Engineer – in – Charge.	8.54	Sqm	987.39	Rupees Nine Hundred Eighty Seven and Thirty Nine Paise	8432.31
17	Fixing tiles in dado ,skirting & rises of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Vitrified Tile (600x600)mm etc complete as per direction of the Engineer – in – Charge.	13.59	Sqm	1190.28	Rupees One Thousand One Hundred Ninety and Twenty Eight Paise	16175.91
18	Priming one coat with water bound cement primer of approved quality over plastered surface including scaffolding staging charges with all materials, taxes, labour charges etc compl.	323.10	Sqm	79.31	Rupees Seventy Nine and Thirty One Paise	25625.06
19	Painting 2 coats with water proofing weather coat of approved shade by means of brush to outside surface of walls with cost, carriage of all materials and cost of all labour with T&P required for the work etc. complete as per direction of the Engineer – in – Charge. In Ground Floor	112.80	Sqm	95.95	Rupees Ninety Five and Ninety Five Paise	10823.16

20	Wall painting two coats with Plastic Emulsion Paint of approved shade on new work to give an even shade including cost, carriage and taxes etc. of all materials required for the work and labour charges etc. complete	210.29	Sqm	102.84	Rupees One Hundred Two and Eighty Four Paise	21626.22
21	Painting two coats with approved enamel paint over a coat of primer of approved quality including cost of enamel paint, primer, brushes & other materials, T. & P. and taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	30.10	Sqm	255.60	Rupees Two Hundred Fifty Five and Sixty Paise	7693.56
22	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect.	7.32	RM	3864.41	Rupees Three Thousand Eight Hundred Sixty Four and Forty One Paise	28287.48
TOTAL CIVIL COST				=		1351148.91

Say 1351149.⁹¹
Rupees Thirteen Lac Fifty One Thousand One Hundred Forty Nine Only *and Ninety one paise only*

My / Our quoted rate of _____ (both in figures & words)
Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs.
..... Only

Total No. of pages (Enclosed) other than DTCN _____ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

P. Behera
2.5.25
J.E. / A.E.
PARJANG BLOCK

Chh
2/5/25
A.E.E.
PARJANG BLOCK

[Signature]
2/5/25
B.D.O
PARJANG

[Signature]
2/5/25
Asst. Engineer
Zilla Parishad, Dhenkanal

Rangrahi
8.5.25
Assistant Executive Engineer
Zillaparisad, Dhenkanal

[Signature]
Addl. Executive Officer (Tech.)
Zilla Parishad, Dhenkanal

BILL OF QUANTITY

NAME OF WORK:-

Construction of Additional Class Room of Visvesvara Vidya Pitha, Mundeilo

AMOUNT PUT TO TENDER :-

Rs 1461149.87

SL. No	ITEM OF WORK	QUANT ITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Earth work in excavation of foundation trenches in HARD soil up to the required depth including dressing and leveling the bed and depositing the excavated materials away from the site with all leads and lifts, T&P labour required for the work etc. complete as directed by the Engineer-In Charge.	61.28	Cum	270.90	Rupees Two Hundred Seventy and Ninety Paise	16600.75
2	Cement concrete (1:3:6) in foundation and plinth using 4 cm. size hard granite crusher broken metal of approved quarry and approved quality including hoisting lowering laying concrete in layers not exceeding 0.15 M. in depth including compacting watering and curing etc, complete including cost ,conveyance, royalties & of all materials and cost of labour etc with T&P required for the work etc. complete as per specification & direction of Engineer-In-Charge.	15.47	Cum	6853.60	Rupees Six Thousand Eight Hundred Fifty Three and Sixty Paise	106025.19
3	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Foundation & Plinth including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc. complete as per specification & direction of Engineer-In-Charge.	9.10	Cum	5867.07	Rupees Five Thousand Eight Hundred Sixty Seven and Seven Paise	53390.34
4	Supplying and filling in foundation and plinth with excavated earth including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	37.53	Cum	150.50	Rupees One Hundred Fifty and Fifty Paise	5648.27
5	Supplying and filling in foundation and plinth with sand including well watering, ramming, including cost, conveyance, royalties and of all materials and cost of all labour with T&P required for the work etc. complete as per direction of Engineer-In-Charge.	28.31	Cum	1436.56	Rupees One Thousand Four Hundred Thirty Six and Fifty Six Paise	40669.01
6	Fly ash Brick masonry in cement mortar (1:6) using Fly ash Bricks of size 23cmx11cmx8cm having crushing strength between 75 Kg / Cm ² after immersing the bricks for six hours in water before use in Superstructure including splays cutting circular molding and corbelling champhering and similar such type including cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work etc. complete etc.	19.15	Cum	5900.07	Rupees Five Thousand Nine Hundred and Seven Paise	112986.34

7	RCC Work M – 20 using 20mm.& down graded black hard crusher broken granite stone chips including hoisting lowering laying and compact concrete by using vibrator watering and curing for 28 days centering shuttering and finishing the exposed surface smooth providing grooves or beads where necessary including cost, conveyance, royalties of all materials and labour with T&P required for the work etc. complete in all respect as per specification & direction of E.I.C					
	A) COLUMN BASE & FOOTINGS	12.57	Cum	7411.70	Rupees Seven Thousand Four Hundred Eleven and Seventy Paise	93165.07 ✓
	B) PLINTH BEAM	4.51	Cum	8283.62	Rupees Eight Thousand Two Hundred Eighty Three and Sixty Two Paise	37359.13 ✓
	C) COLUMN & BEAM	8.56	Cum	16552.26	Rupees Sixteen Thousand Five Hundred Fifty Two and Twenty Six Paise	141687.35 ✓
	D) LINTEL BAND	1.89	Cum	15022.22	Rupees Fifteen Thousand Twenty Two and Twenty Two Paise	28392.00 ✓
	E) CHAJJA	12.20	Sqm	1270.38	Rupees One Thousand Two Hundred Seventy and Thirty Eight Paise	15498.64 ✓
	F) ROOF SLAB	10.81	Cum	14588.02	Rupees Fourteen Thousand Five Hundred Eighty Eight and Two Paise	157696.50 ✓
8	Supplying, providing and straightening the coiled or bent up M.S. / HYSD bars , cutting, bending and tying grills and placing in position with ties, spacers and binding the grills in binding wire 18 to 20 mm. gauge for R.C.C. works as per approved design and drawings with all leads, lifts and delifts and all cost, carriage, taxes of the reinforcement bars and binding wire and labour charges etc. complete as per the specification & direction of Engineer in charge.(Weight of binding wire shall not be considered for payment in any shape at all).	36.56	Qntl	8533.67	Rupees Eight Thousand Five Hundred Thirty Three and Sixty Seven Paise	311990.98 ✓
9	Providing & laying 25mm grading concrete (1:2:2) on roof slab using 6mm size crusher broken hard granite chips including cost, conveyance, royalty & taxes etc. of all materials, mixing & laying concrete, watering & curing, labour charges etc. complete as per the specification & direction of Engineer in charge.	84.52	Sqm	413.30	Rupees Four Hundred Thirteen and Thirty Paise	34932.12 ✓
10	Supplying MS door & window shutter with grills (Framed&Fixed) made out of MS angles, flats and sheets etc of approved design & fabrication including cost, conveyance & taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	520.00	Kg	84.75	Rupees Eighty Four and Seventy Five Paise	44070.00 ✓

11	Labour for fitting and fixing of GI doors, windows and gates as per approved design including fixing of door and windows clamps with cement concrete (1:3:6) using 12mm size hard broken granite chips and curing for 7 days after fixing the clams including cost, conveyance, royalty, taxes etc. of all materials required for the work and labour charges etc. compl	11.89	Sqm	93.32	Rupees Ninety Three and Thirty Two Paise	1109.57
12	Providing 12mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	121.12	Sqm	200.96	Rupees Two Hundred and Ninety Six Paise	24340.28
13	Providing 16mm thick cement plaster (1:6) finished smooth to brick walls after racking out joints including watering and curing etc. complete with cost, conveyance, royalties of all materials and cost of all labour with T & P required for the work complet as per direction of Engineer-In-Charge.	146.05	Sqm	286.45	Rupees Two Hundred Eighty Six and Forty Five Paise	41836.02
14	6 mm thick cement plaster in cement mortar (1 : 4) including closed deep chipping & slurry treatment including cost, conveyance, royalty & taxes etc. of all materials required for the work,watering, curing, labour charges etc. complete	56.87	Sqm	217.63	Rupees Two Hundred Seventeen and Sixty Three Paise	12376.62
15	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitrified tile (600x600)mmetc complete as per direction of the Engineer – in – Charge.	71.37	Sqm	1158.93	Rupees One Thousand One Hundred Fifty Eight and Ninety Three Paise	82712.83
16	Fixing tiles in floors ,treads or steps & landings on 20mm thick bed of cement mortar 1:4 jointed with neat cement slurry mixed with pigment to match the shades of the tiles & polishing including cost of vitrified Industrial Floor tileetc complete as per direction of the Engineer – in – Charge.	9.29	Sqm	986.84	Rupees Nine Hundred Eighty Six and Eighty Four Paise	9167.74
17	Fixing tiles in dado,skirting & rises of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing & polishing using Vitrified Tile (600x600)mmetc complete as per direction of the Engineer – in – Charge.	14.80	Sqm	1189.89	Rupees One Thousand One Hundred Eighty Nine and Eighty Nine Paise	17610.37
18	Priming one coat with water bound cement primer of approved quality over plastered surface including scaffolding staging charges with all materials, taxes, labour charges etc compl.	356.99	Sqm	79.31	Rupees Seventy Nine and Thirty One Paise	28312.88
19	Painting 2 coats with water proofing weather coat of approved shade by means of brush to outside surface of walls with cost, carriage of all materials and cost of all labour with T&P required for the work etc. complete as per direction of the Engineer – in – Charge. In Ground Floor	121.12	Sqm	95.95	Rupees Ninety Five and Ninety Five Paise	11621.46

20	Wall painting two coats with Plastic Emulsion Paint of approved shade on new work to give an even shade including cost, carriage and taxes etc. of all materials required for the work and labour charges etc. complete	235.87	Sqm	102.84	Rupees One Hundred Two and Eighty Four Paise	24256.87
21	Painting two coats with approved enamel paint over a coat of primer of approved quality including cost of enamel paint, primer, brushes & other materials, T. & P. and taxes etc. of all materials required for the work and labour charges etc. complete as per the specification & direction of Engineer in charge.	30.10	Sqm	255.60	Rupees Two Hundred Fifty Five and Sixty Paise	7693.56
TOTAL CIVIL COST				=		1461149.87

Footeen Sixtyone *Eighty nine* Say **1461149.87**
 (Rupees **Fifteen lakh Two thousand One hundred Fourty eight**) Only

My / Our quoted rate of _____ (both in figures & words)
 Excess over / Less than / Equal to the above estimated cost and tendered amount is Rs.....
 Only

Total No. of pages (Enclosed) other than DTCN _____ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machinaries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour cess as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC, TMT High strength steel Fe - 500 like SAIL / TISC

P. Behera
 2.5.25
 J.E. / A.E.
 PARJANG BLOCK

SSR
 21.5.25
 A.E.E.
 PARJANG BLOCK

B.D.Q
 B.D.Q
 PARJANG

[Signature]
 6/5/25
 Asst. Engineer
 Zilla Parishad, Dhenkanal

Rangrahi
 8.5.25
 Assistant Executive Engineer
 Zillaparisad.Dhenkanal

[Signature]
 6/5/25
 Addl. Executive Officer (Tech.)
 Zilla Parishad, Dhenkanal