

Name of the work :
Name of the G.P :
Name of the scheme :

Construction of AWC Building at Padhansahi, Karagola GP, under PM-JANMAN in PVTG AREA
Karagola
PM-JANMAN

Amount put to Tender : 962,587.60

BILL OF QUANTITY

Sl. No.	Description of Work	Unit	Quantity	Estimated Rate in Rs	Rate in Words	Amount
1	Earth work in hard soil within 50m. initial lead and 1.5m. Initial lift including rough dressing and breaking the clods to maximum 5cm. To 7cm. Laying the layers not exceeding 0.30m. In depth etc complete.	CuM	23.04	276.89	Rupees Two Hundred Seventy-six & Eighty-nine paise only	6,379.55
2	Providing and filling clean dry sand of approved quality from approved quarry in foundation and plinth in 6" thick layer well watered and rammed incl. cost, conveyance, royalties and taxes of all materials etc.	CuM	20.81	1216.93	Rupees One Thousand Two Hundred Sixteen & Ninety-three Paise only	25,324.31
3	C.C (1:3:6) using 40mm HG metal of approved quality from approved quarry incl. hoisting, compacting curing, finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials, cost of labour and T&p etc. all complete as per the direction of E.I.C.	CuM	8.11	6862.23	Rupees Six Thousand Eight Hundred Sixty-Two & Twenty-three Paise only	55,652.69
4	Filling in foundation and plinth with excavated materials including water and ramming as directed by the Engineer-in -charge.	CuM	7.68	184.59	Rupees One Hundred Eighty-four & Fifty-nine Paise only	1,417.65
5	R.C.C. work of M - 20 grade with 20 mm and down grade HGCB chips incl. hoisting, laying concrete in layers not exc. 15cm thick, compacting by means of vibrator, curing, finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost, conveyance, royalty & taxes of all materials, cost of labour and T&p etc. all complete as per the direction of E.I.C.					
i)	Column Footings & Pedestals	CuM	4.536	7257.21	Rupees Seven Thousand Two Hundred Fifty-seven & Twenty-one Paise only	32,918.70
ii)	Plinth Bands	CuM	2.675	8127.55	Rupees Eight Thousand One Hundred Twenty-seven & Fifty Five Paise only	21,741.20
iii)	Columns & Beams	CuM	4.998	16520.12	Rupees Sixteen Thousand Five hundred Twenty & Twelve Paise only	82,567.56
iv)	Lintel Bands	CuM	1.605	14920.62	Rupees Fourteen Thousand Nine Hundred Twenty & Sixty-two Paise only	23,947.60
v)	Chajjas	SqM	0.263	14432.40	Rupees Fourteen Thousand Four Hundred Thirty-two & Fourty Paise only	3,795.72
vi)	Roof Slab	CuM	6.30	14432.40	Rupees Fourteen Thousand Four Hundred Thirty-two & Fourty Paise only	90,924.12
6	Cutting, straightening, coiled or bent up T. S. rod for R.C.C. work incl. bending, binding & tying the grills and placing in proper position with cost, conveyance, taxes of binding wire 18 to 20 gauge and T.S. rod, cost of all labour & T&P etc complete as per the direction of E.I.C.	Qtl	18.34	8,065.13	Rupees Eight Thousand Sixty-five & Thirteen Paise only	147,914.48

[Signature]
30/10/25

[Signature]
30/10/25

7	Flyash brick masonry in C.M. (1:6) using brick of size 23cmx11cmx 8cm of crushing strength not less than 75kg/cm ² with dimensional tolerance plus minus 8% after immersing the bricks for six hours before use incl. lowering, placing in position, watering and curing and cost, conveyance, royalties and taxes of all materials, cost of labour & T&P etc. complete as per the direction of E.I.C.(For foundation & plinth) etc all complete.					
A	For Foundation & Plinth	CuM	7.93	5828.54	Rupees Five Thousand Eight Hundred Twenty-eight & Fifty-four Paisa only	46,220.32
B	Super Structure	CuM	22.195	5,861.54	Rupees Five Thousand Eight Hundred Sixty-one & Fifty-four Paisa only	130,096.88
8	Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	KG	215.89	110.00	Rupees Eighty Six & Eighty Two Paisa only	23,747.90
9	Supplying, fitting and fixing steel Angle iron door and windows as per approved design and drawing including all cost of materials and labour etc complete as per direction of Engineer in charge.	KG	404.44	110.00	Rupees Seven Thousand & Zero Paisa only	44,488.40
10	Labour for fitting and fixing doors and windows etc.all complete.	SqM	17.539	70.10	Rupees Seventy & Ten Paisa only	1,229.48
11	6mm thick cement plaster (1:4),finished smooth to R.C.C. surfaces after cleaning the surface incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	13.02	215.50	Rupees Two Hundred Fifteen & Fifty Paisa only	2,805.81
12	16mm thick cement plaster (1:6),finished smooth to brick masonry work in inside surface after cleaning the surface incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	158.59	282.03	Rupees Two Hundred Eighty Two & Three Paisa only	44,727.14
13	12mm thick cement plaster (1:6) for brick masonry work in outside surface after racking out joints incl. watering, curing etc. complete with cost, conveyance, royalties & taxes of all materials, labour and T&P etc complete as per the direction of E.I.C.	SqM	113.731	196.43	Rupees One Hundred Ninety Six & Fourty-three Paisa only	22,340.18
14	Fixing colour Vitrified tiles in dados of size 600mm x600 mm of approved make conforming IS:13755 laid on 12 mm thick cement mortar(1:3)and filling joints with white cement of approved quality including cost of all materials, labour T&P etc rrequired for the work all complete as per direction of Engineer-in-charge.	SqM	6.18	1193.10	Rupees One Thousand One Hundred Ninety-three & Ten Paisa only	7,373.36
15	Supplying, fitting & fixing Vitrified tiles in floors of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials,taxes, labour, T&P, etc. complete as per direction of Engineer-in-charge.	SqM	32.92	1146.27	Rupees One Thousand One Hundred Fourty-six & Twenty-seven Paisa only	37,730.62
16	Fixing colour Glazed tiles in wall on 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles T&P etc rrequired for the work all complete as per direction of Engineer-in-charge.	SqM	20.60	936.18	Rupees Nine Hundred Thirty-six & Eighteen Paisa only	19,285.31

[Signature]
20/10/25

[Signature]
20/10/25

17	Fixing colour Glazed Tiles in floor on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all work all materials, taxes, labour, T&P etc. complete as per direction of Engineer-in-charge.	SqM	4.20	936.18	Rupees Nine Hundred Thirty-six & Eighteen Paise only	3,931.96
18	Fixing chequered tiles in floors, trends or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades including cost for rubbing, polishing & cost of marble tiles	SqM	8.58	734.59	Rupees Seven Hundred Thirty-four & Fifty-nine only	6,302.78
19	Water bound cement priming one coat with primer of approved quality over wall. Data for 93.00 Sqm.	SqM	301.91	80.56	Rupees Eighty & Fifty-six Paise only	24,321.87
20	Distemping two coats with approved shade over a coat of oil bound primer incl. cost of all material, labour and T&P etc. complete.	SqM	196.12	87.93	Rupees Eighty Seven & Ninety-three Paise only	17,244.66
21	Painting two coats with approved paint to doors and windows over a coat of primer incl. cost of all material, T&P and labour etc complete. (for Iron work)	SqM	40.09	259.05	Rupees Two Hundred Fifty Nine & Five Paise only	10,385.31
22	Weather coat painting two coats with approved shade over a coat of oil bound primer incl. cost of all material, T&P and labour etc complete.	SqM	105.79	97.32	Rupees Ninety Seven & Thirty-two Paise only	10,295.48
23	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90m C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm. In 2 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Rmt	6.00	2912.76	Rupees Two Thousand Nine Hundred Six & Fourty Two Paise only	17,476.56
Total						Rs 962,587.60

Rupees Nine Lakh Sixty-two Thousand Five Hundred Eighty-seven & Sixty Paise only

Approved for 23 (Twenty-three) Items only

Total No. of pages (Enclosed) other than DTCN _____ pages.

Notes: The Contractor should not write anything except quoting of percentage, Excess / Less / Equal to Estimate up to two decimal points only.

Conditions: All Materials, Labours, Machinaries & Equipments required to complete the work in all respect be arranged by the Tenderer at his own cost. The Employer will bear no responsibility in this aspect.

N.B.: GST, Income Tax, Royalties, Labour Cess as applicable will be deducted from the bill of the Contractor. For all above works minimum grade of cement shall be OPC, TMT High Strength Steel Fe 500 Like SAIL/ TISC


Block Development Officer,
Kankadahad.


My / Our quoted rate is _____

above tendered amount of Rs. _____

Contractor


30/10/2025
Junior Engineer
Kankadahad Block.


30/10/25
Assistant Executive Engineer
Kankadahad Block.


30/10/25
Block Development Officer
Kankadahad.