

Name of the work :- Construction of Additional Class Room at Nua Bhuban High School, Block-Bhuban, Dist-Dhenkanal

AMOUNT PUT TO TENDER:-

Rs. 2421921.43

Name of The Bidder :-

Contract No :-

SL. No	ITEM OF WORK	QUANTITY	UNIT	RATE	RATE IN WORDS	AMOUNT
1	Brick work with Fly Ash Bricks having crushing strength 75 kg/sq.cm in c.m. 1:6 in super-structure including cost conveyance and royalty of materials curing etc. complete.	62.800	Cum	5863.88	Rupees Five Thousand Eight hundred Sixty-three & Eighty-eight Paise Only	Rs. 368251.66
2	Providing and laying Reinforcement Cement Concrete (M-20) with 20 mm and down graded chips including cost all materials,labours,T & P,curing etc complete (excluding the cost of reinforcement & Centering, shuttering) as per direction of Engineer-in-charge.					
i)	Column & Beam	13.230	Cum	20751.48	Rupees Twenty Thousand seven hundred Fifty-one & forty-eight Paise Only	Rs. 274542.08
ii)	Chajja	28.460	Sqm	1412.26	Rupees One thousand four hundred twelve and twenty-six paise only	Rs. 40192.92
iii)	Roof-Slab	27.370	Cum	15461.11	Rupees Fifteen thousand four hundred sixty-one and eleven paise only	Rs. 423170.58
IV)	Lintel Band	8.880	Cum	13299.56 13299.56	Rupees Thirteen thousand two Hundred ninety-eight and fifty-six paise only	Rs. 118100.09 118091.21
3	Supplying, fitting and placing uncoated HYSD bar reinforcement complete in proper position including cost of binding wire 18 to 20 gauge as per direction of Engg.-in-Charge.	50.30	Qntl	8020.31	Rupees Eight thousand twenty and thirty-one paise only	Rs. 403421.59
4	12mm thick cement plaster in cement mortar (1:6)including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.	213.43	Sqm	197.29	Rupees One hundred Ninety-seven and Twenty-nine paise only	Rs. 42107.60
5	16mm thick cement plaster in cement mortar (1:6) including necessary scaffolding curing etc. as per direction of Engg.-in-Charge.	416.92	Sqm	281.03	Rupees Two hundred eighty-one and three paise only	Rs. 117167.03
6	6mm.thick cement plaster with C.M(1:4) to RCC surface including closed deep chipping and slurry treatment etc. complete as per direction of Engg.-in-Charge.	224.24	Sqm	215.30	Rupees Two hundred fifteen and thirty paise only	Rs. 48278.87
7	Fixing colour Vitrified tiles in floors (Printed Series) of size 600mm x600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar (1:1)and filling joints with white cement of approved quality including cost of all materials, labour T&P etc rrequired for the work all completeas per direction of Engineer-in-charge.	175.41	Sqm	1124.32	Rupees One thousand one hundred twenty-four and thirty-two paise only	Rs. 197216.97
8	Fixing Vitrified tiles in dados (Printed Series) skirting and risers of stepson 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including rubbing and polishing complete as per direction of Engineer-in-charge.	20.15	Sqm	1317.88 1317.38	Rupees One thousand three hundred seventeen and eighty-eight only	Rs. 26555.28 26545.21

	Wall Priming one coats on new work with wall water bound primer of approved shade as per direction of Engg-in-Charge .	833.44 331.41	Sqm	83.40	Rupees Eighty-three and Forty paise only	Rs. (185.09) 69592.20
10	Wall painting two coats on new work with plastic emulsion paint of approved shade . etc. complete as per direction of Engg-in-Charge .	573.98	Sqm	109.70	Rupees One Hundred nine & seventy Paise only	Rs. 62965.61
11	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T & P etc. complete as per direction of Engg-in-Charge .	573.98	Sqm	80.03	Rupees Two Hundred seventy-six and Thirteen paise only	Rs. 45935.62
12	Wall painting two coats on new work with Weather coat paint of approved shade as per direction of Engg-in-Charge.	260.46	Sqm	100.60	Rupees One Hundred & sixty Paise only	Rs. 26202.28
13	Supplying and fixing of steel M.S. grill with all fitting and fixtures including cost of cutting holes in the brick masonry and R.C.C. columns and making good to damage etc, as per direction of Engineer -in -charge.	1536.45	Kg	110.00	Rupees One Hundred ten & nil Paise only	Rs. 169009.50
14	Enamel Painting two coats with enamel paint over one coat of primer of approved quality etc. complete as per direction of Engg-in-Charge .	134.53	Sqm	313.08	Rupees Three Hundred Thirteen & eight Paise only	Rs. 42118.65
15	Provision For Black Board size 12.0x4.0ft	3.00	Nos	5500.00	Rupees Five thousand five Hundred and nil Paise only	Rs. 16500.00
TOTAL						Rs. (2421921.43) 2421921.43

(Ruppees Twenty-four lakh twenty-one thousand Nine Hundred Twenty-one & Forty-three Paise) Only

Approved for 15 (Fifteen) Items Only

Total No. of pages (Enclosed) other than DTCN _____ pages

Notes :- The Contractor should not write any thing except quoting of Percentage , Excess / Less / Equal to the Estimate up to two decimal points only.

CONDITIONS :- All materials, Labour, Machineries and Equipments required to complete the work in all respect be arranged by the tenderer at his own cost . The Employer will bear no responsibility in this aspect.

N.B :- GST, Income Tax, Royalties, Labour Cess, EMF, DMF, additional charges as applicable will be deducted from the bill of the contractor for all above works the minimum grade of cement shall be OPC & TMT High strength steel Fe - 500 like SAIL or equivalent


Asst Engineer,
Block

Block

Bhuban



Asst Exe. Engineer
Bhuban Block


Block Dev. Officer
Bhuban


Asst Engineer
Zilla Parishad, Dhenkanal


Addl EO (Tech.)
Zilla Parishad, Dhenkanal

My/Our Quoted rate is
above tendered amount of Rs


Assistant Executive Engineer (both in figure & Words) Excess over/Less than/Equal to the
Zilla Parishad, Dhenkanal Only

Contractor

Block Development Officer Bhuban